

FILED

Date: 7/14/97 By: PC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 65/15-4A

OREGON CORNER RESTORATION FORM

Section 10 Township 24S Range 4W

County DOUGLAS Date 6-25-97

DOUGLAS COUNTY SURVEYOR

Corner Designation

WEST 1/4 CORNER
SECTION 10

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. #37, #67 AND 1979 BLM RESURVEY

Monument(s) & Accessories Found: (Condition and Source)

3/4" BLM BRASS CAP ON 2 1/2" IRON POST, TOP 1" ABOVE THE GROUND.


BT'S FOUND:

15" W. HEMLOCK, N44°E 10.7, FACE HEALED

15" W. HEMLOCK, S48 1/2° W 18.7, FACE HEALED

MONUMENT AND BT'S ARE IN GOOD CONDITION.

Monument Detail



Monument Set (Procedures and Description)

NONE

New Accessories

NONE MARKED

Location & Comments

THE CORNER IS ON A GENTLY SLOPING NORTH RIDGE. IT IS ABOUT 200' WEST OF A DRAW.

Compass Declination 18°E

Firm/Agency FORD-NESS-

FASSBENDER

Address POB 22135

EUGENE, OR 97402

Party Chief S.P. NESS

Notes M. WILKINSON

Witness _____

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

Steven P. Ness
OREGON
JULY 16, 1987
STEVEN P. NESS
811

TO BE RENEWED
12-31-98

C.S. File No. 65/15-4A

FILED

Date: 7/14/97 By: PC

This survey consists of:

Map: _____

Name: _____

Corner Pt: CS 65/15-48

OREGON CORNER RESTORATION FORM

Section 10 Township 24S Range 4W

County DOUGLAS Date 6-25-97

DOUGLAS COUNTY SURVEYOR

Corner Designation

EAST 1/4 CORNER
SECTION 10

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. # 12

Monument(s) & Accessories Found: (Condition and Source)

2 1/2" DCSD BRASS CAP ON 1/4" I. POST, TOP 14" ABOVE GROUND FOR WITNESS CORNER (ACTUAL CORNER POSITION IS SOUTH 40.0 FEET IN CREEK). THE FOLLOWING BT'S REFERENCE THE WITNESS COR.:


9" D. FIR, N5°09'W 19.5, SCRIBE 'X' ON CHEST HIGH FACE, SCRIBE BT ON LOW FACE.

21" D. FIR, S72°48'E 39.4, FACE HEALED.

20" D. FIR SNAG, S30°43'E 26.1, FACES NOT HEALED SCRIBING WC 1/4

S 11 CS BT VISIBLE. SNAG IS ABOUT 30' TALL.

Monument Detail



Monument Set (Procedures and Description)

NONE

New Accessories

NONE MARKED

Location & Comments

THE CORNER IS IN THE NW CORNER OF A RECENTLY HARVESTED BLM CLEAR-CUT UNIT. IT IS ± 880' EAST OF RIDGE TOP.

Compass Declination _____
Firm/Agency FORD-NESS-FASSBENDER
Address POB 22735 EUGENE, OR 97402
Party Chief S.P. NESS
Notes M. WILKINSON
Witness _____

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

Steven P. Ness

OREGON JULY 14, 1967 STEVEN P. NESS 811

TO BE RENEWED 12-31-98

C.S. File No. 65/15-48

This is A →
new Accessory
7/14/97 (PC)