

**REWITNESSED CORNER FOR
STATE OF OREGON – DEPARTMENT OF FORESTRY**

One quarter corner common to Sections 7 and 8, Township 32 South, Range 6 West,
W.M., Douglas County, Oregon.

ORIGINAL by W. H. Byars, 1881

3" x 3" x 3' Yew post (missing) from which a:

60" Fir S78°E 48 lks.; now down and rotted windfall.
46" Fir N60°W 12 lks.; now 53" in place, bark scribes 1/4 visible.

RESTORATION by Douglas County Surveyor, 1967

Douglas County pipe with brass cap (in place) from which a:

8" Yew S78°E 15.1 ft.; now 11" S64°E, scribes visible.

REWITNESSED from the above pipe and cap:

53" Fir (Original) N60°W 7.92 ft. to aluminum nail in BT face bark scribed
S7BT.
Carsonite Witness Post N35°E 5.05 ft. to base.
Carsonite Witness Post S40°W 3.45 ft. to base

Bearing tree tag on 53" original Fir BT N60°W 7.92 ft.

Magnetic variation set at 20° east.

Dated June 7, 2000

Rewitnessed by Tim VanVleet under my direction.

FILED

Date: 7-10-2000 By: JC

This survey consists of:


Map: _____

Narrative: _____


Corner Rpt: C.S. 65/30-13

DOUGLAS COUNTY
SURVEYOR

Present and witnessed by Ralph C. Hall



James M. McIntosh



Cert exp 12-31-2000

C.S. File No. 65/30-13