

**REWITNESSED CORNER FOR  
STATE OF OREGON – DEPARTMENT OF FORESTRY**

Center West one sixteenth corner for Section 8, Township 32 South, Range 6 West,  
W.M., Douglas County, Oregon.

**ESTABLISHED by A. G. Gibson, 1974**

1 1/2" x 36" galvanized iron pipe with 3" bronze cap (in place) from which a:

- 23" Fir S03°E 61.3 ft.; now 24" x 6' high stump in place, face closed.
- 35" Fir S86°W 72.1 ft.; now 40" in place, face closed.
- 4" x 4" x 72" white painted cedar post S53°E 4.3 ft.; now lying on ground.

**REWITNESSED from the above pipe and cap:**

- 7" Fir S52°E 13.5 ft. to aluminum nail in BT face scribed CW1/16S8BT.
- Carsonite Witness Post S53°W 4.9 ft.
- Reset white painted cedar post N28°W 2.3 ft.

Oregon Department of Forestry metal location poster on 24" Fir stump BT S03°E  
61.3 ft. Also bearing tree tag on 7" Fir BT S52°E 13.5 ft.

Magnetic variation set at 20° east.

Dated June 7, 2000

Rewitnessed by *Tim VanVleet* under my direction.  
Tim VanVleet

FILED


Date: 7-10-2000 By: DC  
This survey consists of:  
Map: \_\_\_\_\_  
Narrative: \_\_\_\_\_  
Corner Rpt: CS 65/30-14

DOUGLAS COUNTY  
SURVEYOR

Present and witnessed by Ralph C. Hall



*James M. McIntosh*



Cert exp 12-31-2000

C.S. File No. 65/30-14