

FILED

Date: 1-5-2001 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: 65/33-18

OREGON CORNER RESTORATION FORM

Section 2 Township 25S Range 8W

County Douglas Date Dec. 7, 2000

DOUGLAS COUNTY  
SURVEYOR

Corner Designation

53 | 52  
---  
510 | 511

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc.


Corner Renewed in 1979 by U.S. B.L.M.

Monument(s) & Accessories Found: (Condition and Source)

Found 3 1/4" Brass Cap on a 2 1/2" iron pipe, buried 1 foot deep in logging road, from which are:  
28" D. Fir BT (record 19"), healed blaze, bears S27°E, 32 3/4 feet.  
14" D. Fir BT, healed blaze, bears S45°W, 49 1/2 feet  
20" D. Fir BT, " " , bears N52°W, 73 3/4 feet. (record 15" diam.).  
16" D. Fir BT, " " , record 10", bears N71°E, 79 1/2 feet.

Monument Detail

Sketch



Monument Set (Procedures and Description)

None.

New Accessories

None. (New Tags.)

Location & Comments

Corner falls in Logging Road, a well used spur.

Compass Declination 20°E

Firm/Agency Shaner Engineering, Inc.

Address P.O. Box 1430 Roseburg Oregon 97470

Party Chief B. Shaner

Notes " "

Witness C. McBean

R. Schneider

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Bruce Shaner

OREGON  
OCT. 4, 1957  
BRUCE A. SHANER  
490

Renews June 30,

C.S. File No. 65/33-18 2002