

David A. Edwards - Professional Land Surveyor

P.O. Box 361
Oakland, OR 97462



(541) 459-0512

SURVEY NUMBER M 136-33

SURVEY NARRATIVE TO COMPLY WITH CHAPTER 209, PARAGRAPH 250, OREGON REVISED STATUTES

SURVEY FOR: Roseburg Resources Co. Seneca Jones Timber Co.
P.O. Box 1088 P.O. Box 2129
Roseburg, Oregon 97470 Roseburg, Oregon 97470

LOCATION: In Section 8, T. 25 S., R. **3** W., W.M. in Douglas
County, Oregon.

PURPOSE: To locate and monument certain boundaries in and
around Section 8 as shown on the accompanying
map.

PROCEDURE: Utilizing ties to the found controlling Gov't.
corners around Section 8, I compute the
subdivision of said Section as shown on the
accompanying map. Random traverses were then run
along the boundaries to be marked. After prudent
adjustment the random points were then offset to
true line and the true line was blazed on each
side and steel posts were set along the line. Red
flagging was placed along all blazed lines and
the blazes painted red. Monuments set on this
survey are described on the accompanying map and
are stamped "L.S. 2339" and according to the 1972
B.L.M. Manual. Bearing trees are scribed
according to said Manual, are measured to the
center of tree at root crown and are situated as
follows:

At the West 1/16 Cor. to Sections 5 and 8:

A 36" diam. Fir bears S. 75° W., 10.46 feet.
A 48" diam. Fir bears N. 40° W., 35.66 feet.

At the NW 1/16 Corner of Section 8:

A 17" diam. Hemlock brs. S. 3° E., 34.65 feet.
A 13" diam. Fir bears N. 39° W., 13.65 feet.

At the CN 1/16 Corner of Section 8:

A 5" diam. Fir bears S. 50° E., 5.80 feet.
A 5" diam. Fir bears S. 53 1/2° W., 21.66 ft.

At the NE 1/16 Corner of Section 8:

A 9" diam. Fir bears S. 39° W., 20.05 feet.
A 15" diam. Fir bears N. 77 1/2° W., 12.11 ft.

FILED

Date: 1/18/2001 By: JP

This survey consists of:

Map: M 136-33

Narrative: CS 65/34-1 A # B

Corner Rpt: CS 65/34-1 A # B

DOUGLAS COUNTY
SURVEYOR

David A. Edwards - Professional Land Surveyor

P.O. Box 361
Oakland, OR 97462



(541) 459-0512

At the CW 1/16 Corner of Section 8:

A 7" diam. Alder bears S. 18° W., 10.25 ft.
A 9" diam. Fir bears N. 53° W., 1.11 feet.

At the West 1/16 Cor. to Sections 8 and 17:

An 18" diam. Fir bears S. 21° W., 42.00 feet.
A 16" diam. Fir bears N. 57° E., 13.49 feet.

At the Center 1/4 Corner of Section 8:

A 10" diam. Fir bears S. 29° W., 6.07 feet.
A 10" diam. Fir bears S. 71° W., 12.05 feet.
An 11" diam. Hemlock brs. N. 18° W., 7.50 feet.
A 10" diam Madrone brs. N. 2° W., 3.00 feet.

At the CE 1/16 Corner of Section 8:

An 8" diam. Cedar bears N. 43° E., 8.15 feet.
A 10" diam. Cedar bears N. 41° W., 22.59 ft.

At the CS 1/16 Corner of Section 8:

An 11" diam. Fir bears S. 58° E., 17.38 feet.
A 10" diam. Hemlock brs. S. 28° W., 3.54 feet.

At the SE 1/16 Corner of Section 8:


A 9" diam. Hemlock brs. N. 55° E., 4.35 feet.
A 12 diam. Alder brs. S. 27° W., 25.00 ft.
(measured to center of tree at top of blaze)

Bearing trees at found controlling corners are as per County re-establishment records.


BASIS OF BEARINGS: 1945 G.L.O. survey as shown on the accompanying map.

EQUIPMENT: Nikon DTM 430 Electronic Total Station.

DATE COMPLETED: January 9, 2001.



David A. Edwards



Expires 12/31/01