

David A. Edwards - Professional Land Surveyor

P.O. Box 361
Oakland, OR 97462

FILED

Date 5/9/2001 By: JP

This survey consists of:

Map: M138-8

Narrative: C565/34-6A+B

Corner Ppt: C565/34-6A+B



(541) 459-0512

DOUGLAS COUNTY
SURVEYOR

SURVEY NUMBER M138-8

SURVEY NARRATIVE TO COMPLY WITH CHAPTER 209, PARAGRAPH 250.
OREGON REVISED STATUTES

SURVEY FOR: Seneca Jones Timber Co.
P.O. Box 2129
Roseburg, Oregon 97470

LOCATION: In Section 2, T. 28 S., R. 4 W., W.M. in Douglas
County, Oregon.

PURPOSE: To locate and monument certain boundaries in and
around Section 2 as shown on the accompanying
map.

PROCEDURE: Utilizing ties to the found controlling Gov't.
corners around Section 2, I compute the
subdivision of said Section as shown on the
accompanying map. A diligent search was made for
original evidence at the 1/4 corner for Sec. 2
only, for Sections 2 and 11 and at the NE corner
of Section 2 with negative results. Random
traverses were then run along the boundaries to
be marked. After prudent adjustment the random
points were then offset to true line and the true
line was blazed on each side and steel posts were
set along the line. Red flagging was placed along
all blazed lines and the blazes painted red.
Monuments set on this survey are described on the
accompanying map and are stamped according to the
1972 B.L.M. Manual. Bearing trees are scribed
according to said Manual, are measured to the
center of tree at root crown and are situated as
follows:

At the North 1/16 Cor. to Sections 1 and 2:

An 8" diam. Cedar bears S. 5° E., 20.42 feet.
A 10" diam. Cedar bears N. 37° W., 7.85 feet.

At the 1/4 Corner to Sections 1 and 2:

(old B.T.) A 23" diam. Pine bears S. 28 1/2° E., 59.4 ft.
(new B.T.) An 8" diam. Pine bears S. 23° W., 29.10 feet.

At the SE Corner of Section 2:

(old B.T.'s) A 46" diam. Cedar brs. N. 57° W., 23.1 feet.
A 16" diam. Fir bears N. 47° E., 9.7 feet.
An 18" diam. Fir bears West, 5.2 feet.
A 32" diam. Fir bears S. 71° E., 30.0 feet.

At the 1/4 Corner to Sections 2 and 11:

A 7" diam. Fir bears N. 58° E., 39.13 feet.
A 39" diam. Fir brs. S. 34 1/2° E., 30.30 feet.
A 10" diam. Fir bears S. 62 1/2° W., 25.40 ft.
A 10" diam. Fir bears N. 66° W., 26.11 feet.

David A. Edwards - Professional Land Surveyor

P.O. Box 361
Oakland, OR 97462



(541) 459-0512

At the SW Corner of Section 2:

(old B.T.'s) A 17" diam. Fir bears S. 41° E., 57.6 ft.
A 22" diam. Fir bears N. 38° E., 111.2 feet.
A 24" Fir snag bears N. 40° W., 5.6 feet

(new B.T.'s) A 12" diam. Fir bears S. 46° W., 26.17 feet.
A 16" diam. Cedar brs. N. 41 1/2° W., 35.27 ft.

At the 1/4 Corner to Sections 2 and 3:

(old B.T.'s) A 21" diam. Cedar bears N. 37° E., 17.6 feet.
A 15" diam. Cedar bears S. 76° W., 9.2 feet.

At the North 1/16 Corner to Sections 2 and 3:

A 7" diam. Fir bears S. 38° E., 11.89 feet.
An 8" diam. Fir bears N. 49° W., 7.12 feet.

At the CN 1/16 Corner of Section 2:

A 16" diam. Fir bears N. 34° E., 19.6 feet.
An 11" diam. Fir bears S. 23° E., 3.4 feet.

At the South 1/4 Corner of Section 35:

(old B.T.'s) A 14" diam. Fir bears N. 33° E., 25.6 feet.
An 11" diam. Fir bears N. 26 1/2° W., 9.8 feet.

At the Southeast Corner of Section 35:

(old B.T.'s) A 22" diam. Fir bears N. 47° E., 57.3 feet.
A 36" diam. Fir bears S. 57° W., 21.8 feet.
A 43" diam. Fir bears N. 58° W., 27.7 feet.


At the NW Cor. Section 2 and SW Cor. Section 35:

As per last renewals.

BASIS OF BEARINGS: G.L.O. original survey as shown on the accompanying map.

EQUIPMENT: Nikon DTM 430 Electronic Total Station.

DATE COMPLETED: April 27, 2001.



David A. Edwards



Expires 12/31/01