

FILED

Date 10-1-2001 By JC

This survey consists of:

Map _____

Narrative _____

Corner Rpt 65/37-22 A & B

MULKINS & RAMBO, LLC

P O BOX 809

NORTH BEND, OR 97459

PHONE (541) 751-8900

FAX (541) 751-8900

**DOUGLAS COUNTY
SURVEYOR**

August 10, 2001

Douglas County Surveyor's Office
Courthouse Room 105-A
Roseburg, OR 97470

RE Corner Renewals

In June of this year we did some survey work for forest management purposes and the following corners were found and upgraded

T 21S , R 8W Section 14

Found a 1954 GLO brass cap the corner of Sections 14, 15, 22, and 23 from which I found the record reference monuments in place I scribed "S23 BT" on a 13" DF - bears S70°E, 10 6 ft and I scribed "S15 BT" on an 18" DF - bears N33°W, 11 7 ft

Found a 1954 GLO brass cap at the 1/4 corner between sections 14 and 23 from which I found a 16" DF with visible scribes - bears N16°E, 11 9 ft , I found a 13" DF with visible scribes - bears S40 ½°E, 26 4 ft (both of these trees were scribed recently by persons unknown), I scribed "1/4 S14 BT" on an 18" DF - bears N75°E, 14 1 ft , I scribed "1/4 S23 BT" on a 17" DF - bears N89°W, 12 0 ft , the record BT's are now rotten stumps

T 21S , R 11W Section 6

Found the record brass cap at the 1/4 corner between Section 6 and 7 set by Robert Ward Jr in 1979 from which I found an 18" DF with a heated face - bears N62°55'W, 25 0 ft , I found a 17" alder with faint bark scribes - bears S30°59'E, 19 6 ft , I bark scribed "1/4 S7 BT" on a 12" alder - bears S28°W, 16 0 ft , I bark scribed "1/4 S7 BT" on a 14" alder - bears S62°E, 14 8 ft

C.S. File No. 65/37-22A

T 31S , R 4W , Section 36

Found a 1957 DSCO brass cap at the 1/4 corner between Section 36 -31-4 and Section 31-31-3 and record BT's per corner #700140 I scribed "1/4 S31 BT" on an 18" DF - bears N17°E, 20 2 ft , I scribed "1/4 S36 BT" on a 10" DF - bears S27°W, 19 8 ft


Found a 1966 DSCO brass cap at the 1/4 corner between Sections 25 and 36 and record BT's per corner #640200 (The record Fir, N12 ½°E, 31 5 ft is now a burnt stump with a healed face) I scribed "BT" at the base and chopped an "X" at dbh on a 4" DF - bears N82°W, 8 8 ft , I scribed "BT" at the base and chopped an "X" at dbh on a 5" DF - bears S22°E, 21 1 ft , A 5 1/2' steel fence post bears 1 0 ft West

If you have any questions about these corners, please give me a call

Troy Rambo, LS 2865



Troy Rambo



Renewal 12-31-02

C.S. File No. 65/37-22B