

OREGON CORNER ~~RESTORATION~~ FORM

Corner No. 12

Section 27 Township 32S Range 7W

County Douglas Date March, 2002

Corner Designation

CW 1/16

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. \_\_\_\_\_

R.S. Van Swearingen, Map M21-61, in 1961.\*

\* (We were requested to redo this survey.)

Monument(s) & Accessories ~~Found~~ Set (Condition and Source)


I set a 3/4" x 40" Iron Rod with a 2 1/2" Alum. Cap, from which a:  
12" Pine BT, I scribed "CW 1/16 BT" bears N66°W,  
22 1/2 feet.

12" B. Fir BT, I scribed "CW 1/16 BT"  
bears S52°W, 40 3/4 feet.

6 Foot Steel Fence Post bears East, 12 feet.

Monument Detail

Sketch



FILED

Date: 3/27/2002 By: sc

This survey consists of:

Map: M 137-35

Narrative: \_\_\_\_\_

Corner Rpt: 65/42-11 Thru 39

DOUGLAS COUNTY  
SURVEYOR

~~Monument Set (Procedures and Description)~~

---



---



---



---

~~New Accessories~~

---



---



---



---

Location & Comments

No evidence of  
V.S. Survey,

Compass Declination 20°E

Firm/Agency Shaner  
Engineering

Address P.O. Box 1430  
Roseburg, OR 97470

Party Chief B. Shaner

Notes " "

Witness Ben Schneider

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Bruce A. Shaner

OREGON  
OCT. 4, 1957  
BRUCE A. SHANER  
430

Renews June 30,

C.S. File No. 65/42-22 2002