

**REWITNESSED CORNER FOR
STATE OF OREGON – DEPARTMENT OF FORESTRY**

One quarter corner common to Sections 11 and 14, Township 23 South, Range 10 West, W.M., Douglas County, Oregon.

ORIGINAL by William H. Byars, 1878

Yew post (missing) from which a;

24" Fir N40E 47 lks; now 36" x 4' high very rotted stump in place, no marks visible.

36" Fir S50°W 15 lks; now rotted flush with ground.

Rewitnessed by Levi C. Walker, 1905

From the original yew post:

8" Fir N30°W 13 lks; now 16" x 2' high stump in place, face closed, added bearing tree tag.

8" Fir S17°W 14 lks; now 20" x 4' high stump in place, face closed, added bearing tree tag.

RESTORTATION by Douglas County Surveyor, 1958

Set iron pipe with brass cap from which a:

14" Fir North 19.8 ft.; now 20" x 2' high stump in place, face closed, added bearing tree tag.

REWITNESSED from the above pipe and cap:

Carsonite witness post N42°E 2.7 ft. to base.

Carsonite witness post S59°W 3.2 ft. to base.


Magnetic variation set at 20° east.

Dated September 19, 2002

Rewitnessed by Tim VanVleet under my direction.
Tim VanVleet



James M. McIntosh



Expiration date of certificate 12-31-02

Present and witnessed by Jennifer M. Griffith

FILED

Date: 11-6-2002 By: JC

This survey consists of:

Map: _____

No. _____

Corner: 64/44-21

DOUGLAS COUNTY
SURVEYOR

C.S. FILED 65/44-21