

FILED

Date: 6/21/2002 By: JP

This survey consists of:

Map: M 137-44

Narrative: _____

Corner Rpt: C565/44-6D


OREGON CORNER RESTORATION FORM

Section 14 Township 30S Range 6W

County Douglas Date June 19, 2002

DOUGLAS COUNTY SURVEYOR

Corner Designation




- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. _____

Monument(s) & Accessories Found: (Condition and Source)

Monument Detail

Sketch



Monument Set (Procedures and Description)

I set a 3/4" x 40" Iron Rod with a 2 1/2" Alum. Cap, from which a:

* Found the 5/8" Iron Rod at S44°W, 6 3/4 feet from Corner. This was set by Mason in 1981.

New Accessories

- 34" D. Fir BT, I scribed "CW 1/16 BT" bears S24°E, 40 feet.
- 14" D. Fir BT, " " " " " " bears N63°W, 20 ± feet.
- 6 Foot Steel Fence Post bears East, 10 feet,
- " " " " " " West, 10 feet.

* 5/8" x 30" Iron was reset along side corner.

Location & Comments

Corner bears South Compass Declination 20°E
190 feet & West 310 Firm/Agency Shaner
feet from fence Engineering, Inc.
Corner. Fence bears Address P.O. Box 1430
East, West & North Roseburg OR 97470
from Fence Corner. Party Chief B. Shaner
 Notes _____
 Witness C. Ranskin

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Bruce A. Shaner

OREGON
OCT. 4, 1957
BRUCE A. SHANER
430

C.S. File No 65/44-6D Renews June 30, '04.