

FILED

Date: 6/4/2003 By: SC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: 65/45-31

DOUGLAS COUNTY  
SURVEYOR

## CORNER NOTES

MAY 2000

BY: TONY HOSTETTER  
P.O. BOX 480  
COOS BAY, OR 97420

FOR: ROSEBURG RESOURCES COMPANY  
P.O. BOX 1088  
ROSEBURG, OR 97470

### **SE CORNER, SECTION 14, T. 25 S., R. 3 W., W.M.** DOUGLAS COUNTY, OREGON

FOUND: 1943 GLO BRASS CAP AND ACCESSORIES DESCRIBED IN DOUGLAS COUNTY SURVEYOR RECORD IN 600400.  
EXCEPT FOR THE FOLLOWING:

48" HEMLOCK STUB @ N42 1/2°E IS GONE.

40" FIR @ N 12 1/2°E IS NOW A SNAG, FACE EVIDENT, BLM TAG.

24" FIR @ S 11 1/2°E IS NOW A STUMP, FACE EVIDENT, BT TAG.



48" FIR @ S 46 1/2°W IS NOW A STUMP, FACE EVIDENT AND BT TAG.

BTS @ N 78°W AND N 37 1/2°W ARE IN GOOD SHAPE.

NEW BTS:

22" HEMLOCK, FACED AND SCRIBED " S13 SW BT", BT TAG,  
BEARS; N 58° E, 17.0 FEET TO 6" SPIKE PLACED IN ROOT COLLAR .

20" HEMLOCK, FACED AND SCRIBED " S14 SE BT", BT TAG,  
BEARS; N 37°W, 6.9 FEET TO 6" SPIKE IN ROOT COLLAR.



6/30/03

C.S. File No 65/45-31