

**Township 21 South, Range 8 West
Section 32**

Witness Corner for NW Corner Section 32: Found 1945 Brass Cap on Iron Pipe firmly set. Original 24" Fir Corner Tree is rotted with old tag but no marks and lies S 0°25' W, 6.6 ft. We Set a 6 foot galvanized steel fence post alongside the old Corner Tree with top painted red.

Old Bearing Trees Taken in Original GLO Survey:

48" rotted Fir Stump, N 62 ½ ° W, 54 links, no marks, with old Bearing Tree Tag. This bearing and distance are from the original corner tree.

All other Original Bearing Trees are gone.

Old Bearing Trees Taken in 1945 by GLO:

44" rotted Fir Stump, S 28° E, 67 links, no marks. This bearing and distance are from the WC.

48" rotted Fir Stump, N 72 ½° W, 52 links, no marks. This bearing and distance are from the WC.

All other 1945 Bearing Trees are gone.


Bearing Trees Taken in 1973 by Douglas County Surveyor:

19" D. Fir, S 22 ½ ° W, 31.0 feet from WC, with healed face and aluminum tag


18" D. Fir, S 7° E, 22.9 feet from WC, with healed face and aluminum tag

15" D. Fir, N 72° E, 14.0 feet from WC, with healed face and aluminum tag

23" D. Fir, N 41° W, 29.2 feet from WC, with healed face and aluminum tag



Gary T. Smither



Expires 6/04

FILED

Date: 3/8/2004 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: 65/49-21

DOUGLAS COUNTY
SURVEYOR

200200

Rec'd Feb 2004

C.S. File No 65/49-21