

**REWITNESSED CORNER FOR
STATE OF OREGON – DEPARTMENT OF FORESTRY**

One quarter corner common to Sections 23 and 26, Township 23 South, Range 10 West, W.M., Douglas County, Oregon.

ORIGINAL by William H. Byars 1879

Maple Post (missing) from which a:

30" Maple N50°E 20 lks.; now 30" x 4 ft. high rotted stump in place, no marks visible.

30" Maple S85°E 30 lks.; missing.

RESTORED by Gregory K. Miller, 1983

2 ½" galvanized iron pipe with 2 ½" brass cap (in place) from which a:

11" Alder S53°E 48.2 ft.; now 16" in place, bark scribes visible.

13" Hemlock S58°W 60.9 ft.; now 16" in place, face closed.

Note: Both bearing trees have Champion Timberlands bearing tree tags.

REWITNESSED from the above pipe and cap:

Carsonite witness post N32°W 2.5 ft. to base.

Carsonite witness post N44°E 2.7 ft. to base.

Metal fence post West 1.1 ft.; no record.


Metal fence post N41°E 1.6 ft.; no record

Magnetic variation set at 20° east.


Dated April 7, 2004

Rewitnessed by Tim VanVleet under my direction.
Tim VanVleet

Rewitnessed by:



James M. McIntosh



James M. McIntosh
63612 Fifth Road
Coos Bay, Oregon

Expiration date of certificate 12-31-04

FILED

Date: 4/30/2004 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: 65/49-31

**DOUGLAS COUNTY
SURVEYOR**

C.S. File No 65/49-31