

David A. Edwards - Professional Land Surveyor

P.O. Box 361
Oakland, OR 97462



DOUGLAS COUNTY OFFICIAL RECORDS
BARBARA E. NIELSEN, COUNTY CLERK

2005-005728



NO FEE

00102713200500057280010018

03/07/2005 12:58:42 PM

PLAT-CORR Cnt=1 Stn=1 RECEIPTCOUNTER
This is a no fee document

Date: 3-7-2005 By: SE

For This survey consists of:

Map: M 142-38

Narrative:

Corner Rpt: CS 65/53-2

DOUGLAS COUNTY
SURVEYOR

AFFADAVIT OF CORRECTION

I, David A. Edwards, being duly sworn, depose and say that I am the surveyor who performed survey number M 142-38 in the survey records of Douglas County, Oregon.

Subsequent to my filing of said survey two original line trees were found along the East line of the Southeast quarter of Section 8 and it was necessary to reposition my South 1/16 corner monument. Said 1/16 corner was moved 2.78 feet North 89° 55' 51" East to be on line between said original line trees. Posts along the East line of the NE 1/4 of the SE 1/4 were also moved to reflect the position of the line trees. Beginning at the SE corner of said Section, the bearings and distances Northerly to said line trees and monuments are as follows:

N.0°02'42"E., 1007.19' to a 30" Cedar line tree;
N.1°02'05"W., 308.37' to my repositioned South 1/16 corner;
N.1°02'05"W., 581.08' to a 62" Fir line tree;
N.0°00'48"E., 734.57' to the East 1/4 corner of Section 8.

David A. Edwards P.L.S. No. 2339
P.O. Box 361
Oakland, Oregon 97462

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 26, 1988
DAVID A. EDWARDS
2339


Renews 12/31/05

NOTARY CERTIFICATE

STATE OF OREGON) ss
County of Douglas)

Subscribed and sworn to before me this 7 day of

MARCH, 2005.



Before me: DAVID A. EDWARDS

APPROVAL

I, Romey Ware, Douglas County Surveyor, hereby certify that I have examined this Affidavit of Correction, and that the changes are permitted in accordance with Chapter 209, Paragraph 255, Oregon Revised Statutes and that this affidavit complies with O.R.S. ~~92.170.~~
209.255

END OF DOCUMENT

Romey Ware, Douglas County Surveyor

C.S. File No 65/53-2