

FILED

Date: 2-18-2005 By: JK

This survey consists of:

Map: \_\_\_\_\_

Name: \_\_\_\_\_

Corner rpt: 65/54-11

DOUGLAS COUNTY  
SURVEYOR

**Township 21 South, Range 9 West  
Section 12**

**Corner Upgrade February, 2005**

Center ¼ Corner for Section 12: At the ¼ corner found 3 " Aluminum Cap on a 2 ½ " aluminum pipe with a steel post near the corner. This monument was established in 1985, county survey number M99-33.32

**Bearing Trees:**

15" D. Fir N 33° E, 1.4 feet, with healed face, spike side center and bearing tree tag.


14" D. Fir S 52° E, 10.7 feet, with healed face, spike side center and bearing tree tag.

**New Bearing Trees:**


23" D. Fir N 4° W, 41.8 feet, scribed T21 R9 C ¼ S12 BT, spike side center and bearing tree tag.

20" D. Fir S 84° W, 32.3 feet, scribed T21 R9 C ¼ S12 BT, spike side center and bearing tree tag.

Submitted by  
Gary T. Smither  
P.O. Box 545  
North Bend, OR 97459  
541-888-2214



*Gary T. Smither*



*Renew 6/06*

C.S. File No 65/54-11