

FILED

Date: MAR 28 2005 by: Jc

This survey consists of:

Map: _____

Notes: _____

Contract: 65/54-14

DOUGLAS COUNTY
SURVEYOR

CORNER NOTES

FEBRUARY 2005

BY: TONY HOSTETTER
63538 PINTAIL DR.
COOS BAY, OR 97420

FOR: WEYERHAEUSER COMPANY
98674 DELLWOOD LANE
COOS BAY, OR 97420

N 1/4 CORNER, SECTION 8, T. 24 S., R. 9 W., W.M.
DOUGLAS COUNTY, OREGON

FOUND: ½" CONDUIT AS DESCRIBED IN WEYERHAEUSER COMPANY
RECORDS.

FROM WHICH:

30" FIR STUMP, OBT, WEYCO TAG,
BEARS; N 33° E, 26.2 FEET TO CENTER. (GLO: N33°E, 25.7 FT.)


40" FIR STUMP, OBT, AXE MARKS, WEYCO TAG,
BEARS; S 05° E, 7.0 FEET TO CENTER. (GLO: S05°E, 5.3 FT.)

NEW BTS:

21" FIR, SCRIBED "S8 1/4 BT", WEYCO TAG,
BEARS: S 31°W, 14.2 FEET TO SPIKE PLACED IN ROOT COLLAR BELOW
SCRIBING.

18" FIR, SCRIBED "S5 1/4 BT", WEYCO TAG,
BEARS: N 40°W, 6.2 FEET TO SPIKE PLACED IN ROOT COLLAR BELOW
SCRIBING.

14" FIR, SCRIBED "S5 1/4 BT", WEYCO TAG,
BEARS: N 00°W, 18.3 FEET TO SPIKE PLACED IN ROOT COLLAR BELOW
SCRIBING.



Tony Hostetter
OREGON
JAN. 19, 1982
TONY HOSTETTER
1975

6-30-05
C.S. File No 65/54-14