

GARY T. SMITHER

Professional Land Surveyor
Certified Water Rights Examiner

FILED

Date: 6-1-2005 By: JC

This survey consists of:

Map: _____

Number: _____

Corner Map: 65/54-20

DOUGLAS COUNTY
SURVEYOR

Township 22 South, Range 8 West Section 1

North ¼ Corner for Section 1 only: Found 1952 Brass Cap on Iron Pipe firmly set. Set 6 foot Steel Post 1.8 feet North of the Brass Cap.

Old Bearing Trees:

50" Fir, S 26° E, 36.3 feet, with healed face and bearing tree tag.


55" Fir, S 49° W, 37.0 feet, uprooted and down.

48" Fir, N 52° E, 22.5 feet, with healed face and bearing tree tag.


New Bearing Trees:

10" D. Fir, S 30° W, 7.7 feet to spike driven in side center, marked "T22 R8 1/4 S1 BT", with bearing tree tag.

9" D. Fir, S 45° E, 16.8 feet to spike driven in side center, marked "T22 R8 1/4 S1 BT", with bearing tree tag.



Gary T. Smither



Renew 6/06

888-2214

FAX and Phone (541) 751-9624

P.O. Box 545, North Bend, OR 97459

C.S. File No 65/54-20