


FILED



GARY T. SMITHER

Date: 8-16-2005 By: JC
The survey is made of:
Map: _____
Name: _____
Corner type: 65/54-30

Professional Land Surveyor

DOUGLAS COUNTY
SURVEYOR

**Township 21 South, Range 11 West
Section 12**

Center 1/4 Corner for Section 12: Found 1984 2" Aluminum Cap on 3/4" Iron Rod firmly set. We set a 6 foot galvanized steel post alongside the monument.

Old Bearing Trees:

58" Cedar S 10° E, 59.0 feet, not scribed, we place new tag.

14" Alder Snag S 58° W, 13.9 feet, with visible bark scribe and tag.

9" Alder Snag N 46° E, 27.8 feet, with visible bark scribe, we place new tag.

New Bearing Trees:

25" Maple, N 18° E, 62.8 to spike driven in side center, Scribed "T21 R11 C 1/4 S12 BT", with bearing tree tag.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Gary T. Smither

OREGON
JANUARY 29, 1991
GARY T. SMITHER
2485

Renew 6/06

FAX and PHONE (541) 888-2214
P.O. Box 545, North Bend, OR 97459

C.S. File No 65/54-30