

FILED

Date: 2/19/2008 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: 65/63-7

DOUGLAS COUNTY  
SURVEYOR

**CORNER NOTES**

January 24, 2008

BY: HOSTETTER LAND SURVEYING  
63538 PINTAIL DR.  
COOS BAY, OR 97420  
FOR: WEYERHAEUSER COMPANY  
98674 DELLWOOD LANE  
COOS BAY, OR 97420

**NW CORNER, SECTION 26, T. 25 S., R. 9 W., W.M.**  
DOUGLAS COUNTY, OREGON

**UNRECORDED HISTORY**

WEYERHAEUSER COMPANY RECORDS, DECEMBER, 1965  
FOUND:

36" HEMLOCK, OBT,  
BEARS: N35 1/2°E, 37.0 FEET.

24" HEMLOCK, OBT,  
BEARS: S23 1/2°E, 26.1 FEET.

30" HEMLOCK, OBT,  
BEARS: S25 1/2°W, 23.5 FEET.

3/4" IRON PIPE, WAS SET IN 1983 (WEYCO RECORD )

**JANUARY 2008**

FOUND: 3/4" IRON PIPE

FROM WHICH:

30" HEMLOCK STUMP, POSSIBLE FACE, AXE MARKS,  
WEYCO TAG, OBT,  
BEARS; S 23° E, 25.7 FEET TO CENTER.


NEW BTS:

12" FIR, WEYCO TAG AND "W" NAIL,  
BEARS: N 70°E, 16.8 FEET TO "W" NAIL PLACED IN ROOT COLLAR  
BELOW TAG.

14" FIR, WEYCO TAG AND "W" NAIL,  
BEARS: S 88°E, 21.0 FEET TO "W" NAIL PLACED IN ROOT COLLAR  
BELOW TAG.

15" FIR, WEYCO TAG AND "W" NAIL,  
BEARS: S 28°E, 14.1 FEET TO "W" NAIL PLACED IN ROOT COLLAR  
BELOW TAG.

14" FIR, WEYCO TAG AND "W" NAIL,  
BEARS: N 30°W, 5.4 FEET TO "W" NAIL PLACED IN ROOT COLLAR  
BELOW TAG.



EXPIRES: 6/30/09  
C.S. File No 65/63-7