

FILED

Date: 8-13-2008 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: 65/63-26

OREGON CORNER RESTORATION FORM

Section 8 Township 23 South, Range 8 West

County Douglas

Date 8 August 2008

DOUGLAS COUNTY
SURVEYOR

Corner Description

Northeast corner
of section 8

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals / Surveys, etc.

Monument (s) & Accessories Found: (Condition and Source)

Found 3" brass cap dated 1981 with the following accessories:

44" D. fir bears N67°W 25.1' – healed face

24" D. fir bears S13°E 15.4' – healed face

15" D. fir bears S34°W 62.0' – healed face


Record 15" D. fir bearing N64°E 5.7" – down, out of position

Monument Detail

Sketch

Monument Set (Procedures and Description)

None



New Accessories

19" D. fir bears N38°E 26.9' – blazed, scribed "T23S R8W S4 BT"

Location & Comments

Corner has steel post
adjacent to it.

Compass Declination 17° East
Firm/Agency Ward NorthWest Inc.

All BT's have red painted
bands and yellow tags.

Address P.O. Box 105
Florence, OR 97439

Party Chief Ron Rice

Notes _____

Witness Josh Reed

Surveyor's Seal



Expires: 12-31-08

C.S. File No 65/63-26