

FILED

Date: 6-2-2010 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 65/69-20

**CORNER REPORT FORM
Douglas County, Oregon**

**DOUGLAS COUNTY
SURVEYOR**

T.25S., R.2W., W.M. C 1/4 Section 20 PLSS 240340

- Condition Report only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced out

Previous Renewals/Surveys:

Monumented by Glenn Baughman under M 56-35, filed January, 1976.

Monument(s) & Accessories Found: (Condition and Source)

A 5/8" iron rod by G. Baughman in 1976 per M 56-35, firmly set, projecting 1" above the ground:

From which a bearing tree by Baughman in 1976:

A 28" Cedar bears N.59 3/4°E., 18.8 feet with scribe marks visible on a partially healed blaze. (Record N.61°E., 18.5 feet)

New Accessories:

A new bearing tree:

A 11" D.fir bears S.15 1/4°E., 21.3 feet scribed "C 1/4 S20 BT".

And new reference monuments:

A 5/8"x 30"iron rod with plastic cap stamped "BTS ENG-SURV" bears S.63°00'42"W., 22.28 feet.

A 5/8"x 30"iron rod with plastic cap stamped "BTS ENG-SURV" bears N.14°49'22"W., 21.08 feet.

Location & Comments:

All new bearing trees have double blazed faces with a brass washer stamped "PLS 1941" nailed into the lower blazed face. Bearings are measured to the center of the tree at the root crown and distances are measured to a nail in the root crown at the side and center of the tree. All bearing trees have a 6" red band painted around the tree and the blazed faces painted red and bearing tree signs nailed to the tree.


Surveyor's Seal:

Firm/Agency:

BTS Engineering & Surveying, Inc.
431 SE Main
Roseburg, OR 97470

Party Chief:

This corner renewal was performed by Lester L. Fanning, PLS 2664, and Scott McCurdy on May 6, 2010.



RENEWAL 12/31/2011

C.S. File No 65/69-20