

**CORNER REPORT FORM
Douglas County, Oregon**

FILED
Date: 6/2/2010 By: JK
This survey consists of: _____
Map: _____
Narrative: _____
Corner Rpt: 65/69-21
**DOUGLAS COUNTY
SURVEYOR**

T.25S., R.2W., W.M. CE 1/16 Section 20 PLSS 260340

___ Condition Report only
___ Not Found
X Renewed
___ Unrecorded
___ Surveyed In
___ Referenced out

Previous Renewals/Surveys:

Monumented by Glenn Baughman under M 56-35, filed January, 1976.

Monument(s) & Accessories Found: (Condition and Source)

A 1" iron pipe by G. Baughman in 1976 per M 56-35, firmly set, projecting 2" above the ground:

From which a bearing tree by Baughman in 1976:

A 18" rotted Hemlock Stump bears N.84 1/4°W., 13.4 feet. (Record N.82°E.)

New Accessories:

New bearing trees:

A 11" D.fir bears S.36 1/2°E., 24.7 feet scribed "CE 1/16 S20 BT".

A 9" D.fir bears S.39 1/4°W., 8.6 feet scribed "CE 1/16 S20 BT".

Location & Comments:

All new bearing trees have double blazed faces with a brass washer stamped "PLS 1941" nailed into the lower blazed face. Bearings are measured to the center of the tree at the root crown and distances are measured to a nail in the root crown at the side and center of the tree. All bearing trees have a 6" red band painted around the tree and the blazed faces painted red and bearing tree signs nailed to the tree.


Surveyor's Seal:

Firm/Agency:

BTS Engineering & Surveying, Inc.
431 SE Main
Roseburg, OR 97470

Party Chief:

This corner renewal was performed by Lester L. Fanning, PLS 2664, and Scott McCurdy on May 6, 2010



RENEWAL 12/31/2011

C.S. File No 65/69-21