

OREGON CORNER RESTORATION FORM

FILED

Date: 11/16/2010 By: J

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/69-57

Section 2, Township 25 South, Range 7 West, W.M.  
County Douglas Date 21 September 2010

DOUGLAS COUNTY  
SURVEYOR

Corner Description

1/4 Corner

Sections 2-3

Condition Report Only

Not Found

Renewed

Unrecorded

Surveyed In

Referenced Out

Previous Renewals / Surveys, etc.

Monument (s) & Accessories Found: (Condition and Source)

Found 2-1/2" BLM brass cap dated 1958 (pronounced lean to the north, which appears to be the condition in which it was set) with the following accessories:

18" D. Fir bears N 39° W 63.7' – healed face

14" Yew snag bears S 66-3/4° W 48.2' - scribing visible

Monument Detail

Sketch

T25S R7W

S3 | S2

1958

Monument Set (Procedures and Description)

None

New Accessories

14" D. Fir bears N 86° W 18.6' – blazed, scribed "1/4 S3 BT"

12" D. Fir bears S 55° E 20.5' – blazed, scribed "1/4 S2 BT"

Location & Comments

Corner has steel post adjacent to it. Compass Declination 16° East  
Firm/Agency Ward NorthWest Inc.


All BT's have red painted bands and yellow tags. Address P.O. Box 105  
Florence, OR 97439

Party Chief Robert Ward

Notes \_\_\_\_\_

Witness Josh Reed

Surveyor's Seal



RENEWS: 12-31-2010

C.S. File No 65/69-57