

FILED

Date: 2-11-2011 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt. CS 65/72-4

# ***CORNER NOTES***

JANUARY 2011

BY: TONY HOSTETTER  
63538 PINTAIL DR.  
COOS BAY, OR 97420

DOUGLAS COUNTY  
SURVEYOR

FOR: WEYERHAEUSER COMPANY  
98674 DELLWOOD LANE  
COOS BAY, OR 97420

***SE CORNER, SECTION 12, T.24 S., R.9 W., W.M.***  
DOUGLAS COUNTY, OREGON

FOUND: ½" CONDUIT (1962 WEYERHAEUSER RECORDS INDICATE THAT 2 ORIGINAL GLO BTS WERE FOUND, A ½" CONDUIT WAS SET AT THAT TIME. )

FROM WHICH:

30" FIR STUMP, POSSIBLE FACE,  
BEARS: S80°E, 9.2 FT TO CENTER.  
( GLO: 16" FIR, S 80°E, 14 LKS )



NEW BTS:

16" FIR, WEYCO TAG,  
BEARS: S 40°E, 10.5 FEET TO 12" SPIKE, PLACED IN TOP CENTER OF STUMP.

16" FIR, WEYCO TAG,  
BEARS: S 08°W, 8.8 FEET TO 6" SPIKE, PLACED IN ROOT COLLAR.

14" HEMLOCK STUMP, WEYCO TAG,  
BEARS; WEST, 17.2 FEET TO 6" SPIKE, PLACED IN ROOT COLLAR.

SE 12-24-9.DOC



EXPIRES: 6/30/11

C.S. File No 65/72-4