

**REWITNESSED CORNER FOR
STATE OF OREGON – DEPARTMENT OF FORESTRY**

Angle Point corner for Section 1, (originally ¼ corner for Sec. 1), Township 23 South, Range 11 West, W.M., Coos and Douglas County, Oregon.

ORIGINAL by William R. Whipple, 1893, Contract No. 612

17" x 12" x 6" stone (missing) from which:

- 50" Burnt Fir N20°E 38 lks.; missing.
- 40" burnt Fir S41°W 31 lks.; missing

RETRACEMENT by Albert Gould, 1910, Contract No. 762

Found sandstone, which he marked A. P., witnessed as described by the Surveyor General, said witness he marked A. P.B. T. (See above)

RESTORATION by Arnold G. Gibson, 1971

Oregon State Board of Forestry 1 ½" x 36" galvanized iron pipe with 3" bronze cap (in place) from which a:

- 28" Fir S38 1/2°E 21.4 ft.; now 33" x 4 ft. high stump in place, face partially visible, added bearing tree tag.
- 25" Fir S14°W 11.0 ft.; now 32" x 5 ft. high stump, face closed, yellow metal location poster.
- 4" x 4" x 72" White painted cedar post S11°W 2.3 ft.; missing.

REWITNESSED from the above pipe and cap:

- Carsonite witness post S05°E 3.70 ft. to base.
- Carsonite witness post S67°W 2.35 ft. to base.

Magnetic variation set at 19° East.


Dated June 16, 2011

Rewitnessed by Tim VanVleet under my direction.
Tim VanVleet

Rewitnessed by:



James M. McIntosh



James M. McIntosh
63612 Fifth Road
Coos Bay, Oregon
Expiration date of certificate 12-31-12

FILED
Date: 7-25-2011 By: JC
This survey consists of:
Map: _____
Narrative: _____
Corner Rpt. CS 65/72-32
DOUGLAS COUNTY
SURVEYOR

Present and witnessed by Ralph C. Hall

C.S. File No 65/72-32