

FILED

Date: 2-8-2012 By: JC

This survey consists of.

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/76-5

DOUGLAS COUNTY  
SURVEYOR

# CORNER NOTES

DECEMBER 2011

BY: TONY HOSTETTER  
63538 PINTAIL DR.  
COOS BAY, OR 97420

FOR: WEYERHAEUSER COMPANY  
98674 DELLWOOD LANE  
COOS BAY, OR 97420

**NE CORNER, SECTION 34, T.23 S., R.9 W., W.M.**  
DOUGLAS COUNTY, OREGON

FOUND: 1/2" ALUMINUM PIPE, LISTED AS 3/4" by Peel  
In 1967 ( CS 55/30 )

FROM WHICH:

22" FIR STUMP, ORIGINAL BT, WEYCO TAG,  
BEARS; N 68°W, 28.4 FEET TO CENTER

28" FIR SNAG, PEEL BT ( CS 55/30 ), WEYCO TAG,  
BEARS; N 67°E, 26.3 FEET TO CENTER.



NEW BTS:

16" FIR, SCRIBED "S26 SW BT", WEYCO TAG,  
BEARS; N 24°E, 4.3 FEET TO SPIKE IN ROOT COLLAR.

12" FIR, SCRIBED "S34 NE BT", WEYCO TAG,  
BEARS; S 65°36'W, 17.6 FEET TO SPIKE IN ROOT COLLAR.

14" FIR, SCRIBED "S27 SE BT", WEYCO TAG,  
BEARS; N 53°15'W, 40.4 FEET TO SPIKE IN ROOT COLLAR.

NE 34-23-9.DOX



C.S. File No 65/76-5

EXPIRES: 6/30/13