

OREGON CORNER RESTORATION FORM

Section 13 Township 22 South, Range 9 West
County Douglas Date 14 May 2012

FILED
Date: 5/15/2012 By: SC
This survey consists of:
Map: _____
Narrative: _____
Corner Rpt: CS 65/76-56

DOUGLAS COUNTY
SURVEYOR

Corner Description

NW Corner
Section 13

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals / Surveys, etc.

Monument (s) & Accessories Found: (Condition and Source)

Found 1-1/4" iron pipe with screwed on pipe cap, marked 11 | 12
14 | 13

- A fir, 21 ins. diam., bears S. 39 1/2° E., 7 1/2 lks. dist., with healed blaze.
(Found a 27" diam. fir with a healed blaze)
- A fir, 17 ins. diam., bears S. 26 3/4° W., 45 1/2 lks. dist., with healed blaze.
(Found a 23" diam. fir with a healed blaze)
- A fir, 16 ins. diam., bears N. 51 3/4° E., 19 1/2 lks. dist., mkd. T22S R9W S12 BT.
(Found a 18" diam. X 6' tall fir stump with a healed face)
- A twin fir, 23 ins. diam., bears N. 33 1/2° W., 40 1/2 lks. dist., mkd. T22S R9W S11 BT.
(Found a 27" diam. X 5' tall twin fir stump with a healed face)

Monument Detail

Sketch

Monument Set (Procedures and Description)

None


New Accessories

None

Location & Comments

Corner has steel post _____ Compass Declination 16° East
adjacent to it. _____ Firm/Agency Northwest Land
All BT's have red painted _____ Surveying Inc.
bands and yellow tags. _____ Address P.O. Box 2827
_____ Florence, OR 97439
_____ Party Chief Ron Rice
_____ Notes _____
_____ Witness Jason Collver

Surveyor's Seal



RENEWS: 12-31-2012

C.S. File 65/76-56