

**REWITNESSED CORNER FOR
STATE OF OREGON – DEPARTMENT OF FORESTRY**

North 1/16 Corner Section 2 (East side), Township 23 South, Range 10 West, W.M.,
Douglas County, Oregon.

ESTABLISHED by A.G. Gibson, 1958

Oregon State Board of Forestry 1½” x 36” galvanized iron pipe with 3” bronze cap;
now a 5/8” iron rod with plastic cap marked PLS 2103, (in place) from which a:

28” Fir (1958) S16°W 24.2 ft.; now 19” x 3 ft. high rotted stump in place, axe
work on bark visible.

38” Fir (1958) N39°W 36.0 ft.; now 30” x 3 ft. high rotted stub in place, no
marks visible.

ESTABLISHED by J. M. McIntosh, 2007 (See Survey No. M153-7)

Moved the 1958 Oregon State Board of Forestry 1½” x 36” galvanized iron pipe with
3” bronze cap N05° 57’ 37” E 4.39 ft. and replaced it with a 5/8” x 36” iron rod with
plastic cap marked PLS 2103 (in place). From the 1½” galvanized iron pipe with 3”
bronze cap a:

14” Fir S88°W 23.9 ft.; now 15” x 5 ft. high stump in place, scribes visible,
Bearing tree tag.

10” Fir S62°E 3.1 ft.; now 11” in place, scribes visible, Bearing tree tag.

Carsonite witness post N60°W 2.2 ft.; in place.

White Painted Cedar Post N41°E 2.0 ft.; in place.

REWITNESSED from the above pipe and cap:

Carsonite witness post S39°W 2.9 ft. to base.

Magnetic variation set at 19° east.


Dated May 12, 2012

Rewitnessed by Tim VanVleet under my direction.
Tim VanVleet

Rewitnessed By:



James M. McIntosh



James M. McIntosh
63612 Fifth Road
Coos Bay, Oregon
Expiration date of certificate 12-31-12

FILED

Date: 6-4-2012 By: JC
This survey consists of:

Map: _____

Narrative: _____

Corner Ref: CS 65/76-58

DOUGLAS COUNTY
SURVEYOR

Present and witnessed by Ralph C. Hall

C.S. File No 65/76-58