

OREGON CORNER RESTORATION FORM

Section 5 Township 31 South, Range 9 West  
County Douglas Date 8 June 2012

FILED  
Date: 6/11/2012 By: JC  
This survey consists of:  
Map: \_\_\_\_\_  
Narrative: \_\_\_\_\_  
Corner Rpt: CS 65/77-5

DOUGLAS COUNTY  
SURVEYOR

Corner Description

NE Corner  
Section 5

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals / Surveys, etc.

Monument (s) & Accessories Found: (Condition and Source)

Found – 2 ½ DCSO brass cap dated 1965

- 13" D. Fir, N 50° E, 6.6 ft., shows good scar – Missing
- 40" D. Fir, S 39 ½° W, 50.8 ft., shows fair scar – Found 40 stump with no marks
- 15" D. Fir, S 85 ¾° W, 24.4 ft., shows good scar – Missing
- 12" Fir, down, N 85° W, 39.6 ft., opened for scribe "BT" – Missing
- 34" D. Fir, N 71° W, 42.5 ft., scribed T30S R9W S32 CS BT – Missing

Monument Detail

Sketch

Monument Set (Procedures and Description)

None


New Accessories

- 11" D. Fir bears S 58° W 31.0 ft. blazed, scribed T31S R9W S5 BT
- 14" D. Fir bears N 79° W 21.4 ft. blazed, scribed T30S R9W S32 BT
- 13" D. Fir bears N 28° E 25.8 ft. blazed, scribed T30S R9W S33 BT
- 9" Madrone bears S 72° E 3.7 ft. blazed, scribed T31S R9W S4 BT

Location & Comments

Corner has steel post \_\_\_\_\_ Compass Declination 16° East  
 adjacent to it. \_\_\_\_\_ Firm/Agency Northwest Land  
All BT's have red painted \_\_\_\_\_ Surveying Inc.  
bands and yellow tags. \_\_\_\_\_ Address P.O. Box 2827  
 \_\_\_\_\_ Florence, OR 97439  
 \_\_\_\_\_ Party Chief Ron Rice  
 \_\_\_\_\_ Notes \_\_\_\_\_  
 \_\_\_\_\_ Witness Jason Collver

Surveyor's Seal



RENEWS: 12-31-2012

C.S. FILE 65/77-5