

FILED

Date: 9-18-2012 By: JC

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: CS 65/77-38

DOUGLAS COUNTY
SURVEYOR

OREGON CORNER RESTORATION FORM

Section 33 Township 24 South, Range 2 West

County Douglas

Date 6 September 2012

Corner Description

NW Corner

Tract 37

Condition Report Only

Not Found

Renewed

Unrecorded

Surveyed In

Referenced Out

Previous Renewals / Surveys, etc.

Monument (s) & Accessories Found: (Condition and Source)

Found 2" dia. Iron post with BLM brass cap dated 1963

12" Hemlock, N.83°E., 62.6 ft., (rec. N.81½°E., 62.0 ft.) to center of tree, scribing visible, BLM tag (Found 26" Hemlock with healed face)

10" Yew, S.46°E., 68.3 ft., (rec. S.47½°E., 67.3 ft.) to center of tree, scribing visible, BLM tag (Not Found)

46" Fir, S.42°E., 57.6 ft., with "W" nail & plate. (Found 46" stump with nail and plate)

58" Fir, S.87°E., 65.4 ft., with "W" nail & plate. (Found 58" stump with nail and plate)

Monument Detail

Sketch

Monument Set (Procedures and Description)

None

New Accessories

15" D. Fir bears S60°E 20.0 ft., scribed TR37 S33 BT

Location & Comments

Corner has steel post _____ Compass Declination 16° East

adjacent to it. _____ Firm/Agency Northwest Land

All BT's have red painted _____ Surveying Inc.


bands and yellow tags. _____ Address P.O. Box 2827
_____ Florence, OR 97439

_____ Party Chief Ron Rice


_____ Notes _____

_____ Witness Jason Collver

Surveyor's Seal



Ronald L. Rice



RENEWS: 12-31-2012

C.S. FILE 65/77-38