

OREGON CORNER RESTORATION FORM

Section 22 Township 30 S. Range 9W  
 County Douglas Date 10/26/12

FILED

Date 11/24/2012 By: JC  
 This survey consists of:  
 Map: \_\_\_\_\_  
 Narrative: \_\_\_\_\_  
 Corner Rpt: CS 65/77-50

Corner Designation

Original Line Tree  
 North 5.7 Chains  
 (376.2 Ft.) of Quarter  
 Corner Between  
 Sections 22 & 23

- \_\_\_\_\_ Condition Report Only
- \_\_\_\_\_ Not Found
- X Renewed
- \_\_\_\_\_ Unrecorded
- \_\_\_\_\_ Surveyed In
- \_\_\_\_\_ Referenced Out

**DOUGLAS COUNTY  
 SURVEYOR**


Previous Renewals/Surveys, etc.

Original GLO Field Notes Field in Douglas County Surveyors Office Pg. 7391.


Accessories Found: (Condition and Source)

Monument Detail

5/8" I.R. With Orange Plastic Cap  
 Marked Lone Rock Timber PLS 2291



- Legend:
- Found Original Line Tree Snag
  - /— Blazed Line
  - ( ) Original GLO Field Notes



Monument Found

Found Original 24" Line Tree Now 40" Snag With Visible Marks on North and South Faces

New Accessories

- Set 5/8" X 40" Iron Rod With Orange Plastic Cap Marked Lone Rock Timber PLS 2291 on North Face of Original Line Tree
- 12" Douglas Fir Bears N5°E 28.7 Ft. To Middle of Line Tree and 26.7 Ft. to Iron Rod We Scribe BT and Nail Aluminum Bearing Tree Tag To The Tree
- 9" Douglas Fir Bears S85°E 21.3 Ft. To Middle of Line Tree and 21.2 Ft. to Iron Rod We Scribe BT and Nail Aluminum Bearing Tree Tag To The Tree

Location & Comments

Found original 24" line tree now a 40" snag with visible marks.  
We reference line tree by setting a 5/8" X 40" iron rod with orange plastic cap on north face of line tree and making two bearing trees to line tree.

Bearing Basis Bearing is Magnetic  
 Firm/Agency Lone Rock Timber Co.  
 Address P. O. Box 1127  
Roseburg, Ore. 97470  
 Party Chief Ken W. Hoffine  
 Notes G. Angiolet  
 Witness G. Angiolet

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Ken W Hoffine*  
 OREGON  
 JULY 16, 1987  
 KEN W. HOFFINE  
 PLS 2291

EXPIRES 6-30-13 CS 65/77-50