

FILED

OREGON CORNER RESTORATION FORM

Date: 10-18-2013 By: XC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/80-22

Section 19 Township 20 South, Range 7 West  
County Douglas Date 18 October 2013

DOUGLAS COUNTY  
SURVEYOR

Corner Description

Closing Corner  
Sections 19, 30

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals / Surveys, etc.

Monument (s) & Accessories Found: (Condition and Source)

Found 2-1/2" GLO brass cap, dated 1954, with the following accessories:

Burned Maple 12" dia., bears N.40°W., 43 lks. dist., with burned out blaze, no scribe mark visible. (Missing)

Burned Fir 48" dia., bears N.50½°E., 52 lks. dist., with illegible scribe marks visible on partially healed and burned blaze. (Found 48" fir stump, scribing visible)

Burned Hemlock 10" dia., bears S.17°E., 44 lks. dist. with illegible scribe marks visible on partially healed and burned blaze. (Missing)

Burned Fir 37" dia., bears S.38°E., 79 lks. dist., mkd. T20S R7W S30 BT. (Found 37" fir stump, no marks)

Monument Detail

Sketch

Monument Set (Procedures and Description)

None

New Accessories

17" D. Fir bears S 4° E 15.2 ft. – blazed, scribed T20S R7W S30 CC BT

15" D. Fir bears N 81° E 20.0 ft. – blazed, scribed T20S R7W S19 CC BT

Location & Comments

Surveyor's Seal

Corner has steel post \_\_\_\_\_ Compass Declination 16° East

adjacent to it. \_\_\_\_\_ Firm/Agency Northwest Land


All live BT's have red painted \_\_\_\_\_ Surveying Inc.

bands and yellow tags. \_\_\_\_\_ Address P.O. Box 2827  
\_\_\_\_\_ Florence, OR 97439


\_\_\_\_\_ Party Chief Ron Rice

\_\_\_\_\_ Notes \_\_\_\_\_

\_\_\_\_\_ Witness \_\_\_\_\_



*Ronald L. Rice*



RENEWS: 12-31-2014

100300 - T20-7  
700319 - T20-8

C.S. FILE CS 65/80-22