


Index

CORNER RECORD (SEARCH)

File No. V-9 PROJ. NO. ELK CORNER SECTION
 TOWNS. 31 S RANGE 1 W R.D. TILLER COUNTY DOUGLAS GCDB# 300200
 MERID. W.M. FOREST UMPQUA STATE OREGON



DESCRIBE CORNER MONUMENT FOUND
 FOUND 3" BRASS CAP ON 2-1/2" IRON PIPE, PROJECTING 1 INCH ABOVE A RING OF STONE, NEAR THE CENTER OF A DIRT PRIVATE ROAD

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

DIA	TYPE	BEARS	DIST	FACE/MARKINGS
23"	FIR	N41°30'E	27.6 FT	HEALED DOUBLE BLAZE
9"	P.PINE SNAG	S50°30'E	79.0 FT	HEALED DETACHED FACE, LEANING NW
21"	P.PINE	S15°45'W	45.4 FT	HEALED DOUBLE BLAZE, LEANING SW
11"	FIR	N56°15'W	27.7 FT	HEALED DOUBLE BLAZE, LEANING NW

Obj. Ident. _____
 Ident. By _____
 Signature _____

PLANE COORDINATE POSITION DATA
 State _____ Zone _____
 North _____
 West _____
 Estab. By _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
 CORNER FALLS ON FLAT GROUND, IN A ROAD SURFACE, SURROUNDED BY A WIDE RING OF STONES. TAKE COUNTY ROAD 1A 3/4 MILE TO A PULL OUT JUST PAST A BRIDGE, OPPOSITE PULLOUT IS GATED ROAD, FOLLOW ROAD OVER 1/2 MILE TO CORNER.

Signature _____ Title _____ Division _____ Headquarters _____

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT
 BRUSH CLEARED AROUND MONUMENT AND TO BT'S
 "LAND LINE" FLAGGING TIED ON MONUMENT AND GUARD POSTS

REGISTERED PROFESSIONAL LAND SURVEYOR

John Ransom

OREGON
 JULY 21, 1992
 JOHN C. RANSOM
 2561

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE
 MARKED: A 9" P.PINE BEARS, S36°15'E - 76.7 FT, MARKED "T31SR1WS33" "BT" ON A DOUBLE BLAZE, WITH BRASS WASHER MARKED "LS2561" IN LOWER BLAZE BETWEEN B & T.
 RED PAINT APPLIED TO BT. FACES AND A 6" BAND AT HEAD HEIGHT, BT'S INCLUDE BT & SURVEY MONUMENT TAGS

DONE BY: Jonathan Drew TITLE LSIT DATE 1/16/2014 PLS NO./AGENCY/STATE _____
 Certified Cor. Record Prepared? YES Filed At: DOUGLAS CO. DATE _____

REMARKS
 MEASUREMENTS TO ACCESSORIES MADE WITH A LEICA 1103+ TOTAL STATION WITH REFLECTORLESS EDM TO ALUMINUM NAIL SET AT SIDE CENTER, BASIS OF BEARING FROM M81-59, BEING N00°13'59"E FROM AN OPEN TRAVERSE RUN BETWEEN THIS CORNER AND THE S 1/16 CORNER TO THE NORTH. MEASURE=1337.42'=RECORD. MAINTAINED PROPERTY LINE NORTH 1/4 AND WEST 1/8 MILES

Index File No V-9 T. 31 S R. 1 W M. W.M. Proj No. ELK Cor. SECTION

C.S. File No 65/85-9