


Index

CORNER RECORD (SEARCH)

File No. N-1 PROJ. NO. ELK CORNER SECTION
 TOWNS. 32 S RANGE 1 W R.D. TILLER COUNTY DOUGLAS GCDB# 100400
 MERID. WM FOREST UMPQUA STATE OREGON

CORNER DIAGRAM 	DESCRIBE CORNER MONUMENT FOUND FOUND 3-1/2" BLM BRASS CAP FLUSH IN MOUND OF STONE																									
Obj. Ident. Ident. By Signature _____	DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND <table border="1"> <thead> <tr> <th>DIA</th> <th>TYPE</th> <th>BEARS</th> <th>DIST</th> <th>FACE/MARKINGS</th> </tr> </thead> <tbody> <tr> <td>10"</td> <td>YEW</td> <td>(N45E)</td> <td>(9.9 FT)</td> <td>SCRIBE ON PART. HEALED DOUBLE BLAZE</td> </tr> <tr> <td>19"</td> <td>YEW</td> <td>(S46E)</td> <td>(18.3 FT)</td> <td>SCRIBE ON PART. HEALED DOUBLE BLAZE</td> </tr> <tr> <td>23"</td> <td>W.FIR</td> <td>(N56W)</td> <td>(82.7 FT)</td> <td>HEALED DOUBLE BLAZE</td> </tr> <tr> <td>17"</td> <td>FIR</td> <td>(S70W)</td> <td>(22.6 FT)</td> <td>HEALED DOUBLE BLAZE</td> </tr> </tbody> </table> <p>() = RECORD PER 2002 BLM RECORD</p>	DIA	TYPE	BEARS	DIST	FACE/MARKINGS	10"	YEW	(N45E)	(9.9 FT)	SCRIBE ON PART. HEALED DOUBLE BLAZE	19"	YEW	(S46E)	(18.3 FT)	SCRIBE ON PART. HEALED DOUBLE BLAZE	23"	W.FIR	(N56W)	(82.7 FT)	HEALED DOUBLE BLAZE	17"	FIR	(S70W)	(22.6 FT)	HEALED DOUBLE BLAZE
DIA	TYPE	BEARS	DIST	FACE/MARKINGS																						
10"	YEW	(N45E)	(9.9 FT)	SCRIBE ON PART. HEALED DOUBLE BLAZE																						
19"	YEW	(S46E)	(18.3 FT)	SCRIBE ON PART. HEALED DOUBLE BLAZE																						
23"	W.FIR	(N56W)	(82.7 FT)	HEALED DOUBLE BLAZE																						
17"	FIR	(S70W)	(22.6 FT)	HEALED DOUBLE BLAZE																						
PLANE COORDINATE POSITION DATA State _____ Zone _____ North _____ West _____ Estab. By _____	DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER CORNER FALLS ON SLIGHT NORTH SLOPE AT CORNER OF RECENT PRIVATE CLEAR CUT, TAKE HIGHWAY TO INTERSECTION OF CLOSED PRIVATE LOGGING ROAD ON SOUTH'LY SIDE OF CLEAR CUT UNIT, FOLLOW ROAD ON FOOT WEST-SOUTHWEST TO END, THEN SOUTHWEST TO TIMBER CORNER.																									

Signature _____ Title _____ Division _____ Headquarters _____ Date 7100-52 (3/68)

CORNER RECORD (PERPETUATION)

REGISTERED PROFESSIONAL LAND SURVEYOR

John Ransom

OREGON
 JULY 21, 1992
JOHN C. RANSOM
 2561

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

BRUSH CLEARED AROUND MONUMENT AND TO BT'S
 "LAND LINE" FLAGGING TIED ON MONUMENT AND GUARD POSTS

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

NO NEW ACCESSORIES ADDED
 NEW NAILS IN BT TAGS AND PAINTED FACES & 6 INCH BAND AT HEAD HEIGHT

DONE BY: Jonathan Drew TITLE LSIT DATE 9/11/2013 PLS NO./AGENCY/STATE JOHN RANSOM, PLS2561
 Certified Cor. Record Prepared? NO Filed At: _____ DATE _____

REMARKS

PROPERTY LINE MAINTINED EAST .5 MILES

Index File No N-1 T. 32 S R. 1 W M. WM Proj No. ELK Cor. SECTION

C.S. File No 65/85-30