

FILED

Date: 1-20-2015 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/87-2

CORNER REPORT FORM

Section 34 Township 22 S Range 7 W  
Douglas County Date 1/5/15  
PLSS Number 400200

DOUGLAS COUNTY  
SURVEYOR

CORNER DESIGNATION

NW corner of Section 34.

- Condition Report only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced out

Previous Renewals/Surveys, etc:

Orig. G.L.O. Byars 1871.  
Haines set T-iron on M 38-69.

Monument(s) & Accessories Found: (Condition and Source)

Found T-iron.  
40" diam. Fir stump bears S.30°E., 16.5'. O.B.T. per Haines.  
A 13" diam. Fir with healed blaze bears N.71°E., 19.7'. ( Haines B.T. )  
Haines' other two B.T.'s are stumps.

Monument Detail

Sketch

Standard Haines T-iron with no brass washer.

Monument Set (Procedures and Description)

N/A

New Accessories

A 14" diam. Hemlock scribed "T22S R7W S34 BT" bears S.62°E., 37.5 feet.  
A 5" diam. Hemlock scribed "T22S R7W S33 BT" bears S.70°W., 25.1 feet.  
A 6 foot steel post is set 2 feet East.

No suitable trees in Section 28.

Surveyor's Seal

Location & Comments

Compass Declination 15° East


Firm/Agency: David Edwards Land Surveying

Address: P.O. Box 361  
Oakland, OR. 97462

Party Chief: B. Miller

Notes: \_\_\_\_\_

Witness: E. Sprinkle



Renews 12/31/15

C.S. File CS 65/87-2