

FILED

Date: 3-30-2015 By: X

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt: C565/87-37

DOUGLAS COUNTY
SURVEYOR

CORNER REPORT FORM

Section 32 Township 31 S Range 5 W
Douglas County Date 3/20/2015
PLSS Number 240100

CORNER DESIGNATION

South 1/4 corner of
Section 32 only.

- ___ Condition Report only
- ___ Not Found
- X Renewed
- ___ Unrecorded
- ___ Surveyed In
- ___ Referenced out

Previous Renewals/Surveys, etc:

Original by George W. Hyde in 1855.

BLM resurvey by Gawron and McDonald in 1962. Survey by T.H. Mehl: C.S. 55/15.

Monument(s) & Accessories Found: (Condition and Source)

Found 1962 B.L.M. brass capped iron pipe.

B.L.M. BT S. 68 1/2° E. is a windfall.

The other two B.L.M. B.T.'s are at the record positions but are snags.

Monument Detail

Sketch

Standard B.L.M. brass capped iron pipe.

Monument Set (Procedures and Description)

N/A

New Accessories

A 17" diam. Fir bears N. 54° E., 25.3 feet.

A 14" diam. Fir bears N. 76° W., 25.46 feet.

Both scribed "T31S R5W 1/4 S32 BT"

Measurements are to 16d nails driven side-center
at root crown.

A 14" diam. Fir with a painted blaze bears S. 36° E., 2.70 feet.

Location & Comments

Compass Declination 15° East

Firm/Agency: David Edwards Land Surveying


Address: P.O. Box 361

Oakland, Oregon 97462

Party Chief: Brant Miller

Notes: _____

Witness: Eric Sprinkle



Renews 12/31/15

C.S. FILE 65/87-37