

FILED

Date: 11-3-2015 By: X  
This survey consists of:  
Map: \_\_\_\_\_  
Narrative: \_\_\_\_\_  
Corner Rpt: CS 65/89-52

**CORNER NOTES**

June 9, 2015

**DOUGLAS COUNTY  
SURVEYOR**

BY: TONY HOSTETTER  
63538 PINTAIL DR.  
COOS BAY, OR 97420

FOR: WEYERHAEUSER COMPANY  
98674 DELLWOOD LANE  
COOS BAY, OR 97420

**W 1/4 CORNER, SECTION 27, T.25 S., R.9 W., W.M.**  
COOS COUNTY, OREGON

FOUND: STEEL "T" FENCE POST, 2 FEET OUT OF GROUND. EVIDENTLY SET BY WEYCO BUT NOT LISTED IN THEIR RECORDS.

FROM WHICH:

41" FIR STUMP, FACE EVIDENT, LISTED IN WEYCO RECORDS AS OBT, TAG AND "W" NAIL, ( GLO: N15°W, 29LKS ) BEARS; N15°W, 18.0 FEET TO CENTER.

NEW BTS:


24" FIR, BT TAG,  
BEARS: N 40°E, 0.7 FEET TO 6" SPIKE, PLACED BELOW TAG.

16" FIR, BT TAG,  
BEARS: S 15°E, 28.3 FEET TO 6" SPIKE, PLACED BELOW TAG.

18" FIR, BT TAG,  
BEARS: S 16°W, 42.4 FEET TO 6" SPIKE, PLACED BELOW TAG.

18" FIR, BT TAG,  
BEARS: N 16°W, 14.2 FEET TO 6" SPIKE, PLACED BELOW TAG.

W QU 27-25-9.DOC

  
EXPIRES: 6/30/17

C.S. File No 65/89-52