

FS INDEX ID: C-3

# CORNER INVESTIGATION REPORT

CORNER: C1/4                      GCDB ID: 140640  
TOWNSHIP: 31 S                    STATE: OREGON  
RANGE: 1 W                        COUNTY: DOUGLAS  
SECTION: 6                         FOREST: UMPQUA  
MERIDIAN: W.M.                 DISTRICT: TILLER  
NFSL PROPERTY BOUNDARY CORNER?:  YES  NO

DATE: 6/1/2015

HISTORY OF VISITATIONS:

1967-G.S. BAUGHMAN, M34-23, CS 55/41  
 1979-KURT WEAVER, M81-28, CS 58/216  
 1980-L.HERZSTEIN, USFS CORNER CARD

LINE(S) POSTED: NORTH-1967    WEST-1967  
MAINTAINED:    NORTH-1980    WEST-2015  
GUARD POST(S):    NORTH            WEST

CORNER HISTORY:

(1967)-ESTABLISHES C1/4 BY INTERSECTION, SETS BRASS CAP/IRON PIPE & 2 BT'S.  
 (1979)-FINDS BRASS CAP/IRON PIPE & 2BT'S.  
 (1980)-FINDS BRASS CAP/IRON PIPE & 2BT'S.

MONUMENT FOUND/SET:

FOUND A 2-1/2" BRASS CAP ON 2-1/2" GALVANIZED IRON PIPE, PROJECTING 2 INCHES ABOVE THE GROUND.

RECORD CORNER ACCESSORIES:


A 24" FIR WITH A HEALED SINGLE BLAZE.  
 A 35" FIR WITH A HEALED SINGLE BLAZE.

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES NEEDED



*Jonathan B. Drew II*



EXPIRES: 12/31/2015

RECORD MEASUREMENTS:

N83°30'E-22.6')1967,(N81°31'E-22.9')1979  
 (S83°W-51.2')1967,(S81°24'W-51.7')1979

METHOD OF MEASUREMENT:

NO NEW MEASUREMENTS TAKEN.  
 GUARD POST(S) PRESENT, NOT MEASURED.

FILED AS CONDITION REPORT

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

GEODETIC COORDINATES:

LATTITUDE: N 42° 54' 33.636"  
 LONGITUDUE: W 122° 52' 23.314"  
 ELIPSOID HEIGHT: 3060 FT  
 DATUM: WGS84

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D  
 SPRINGFIELD, OREGON 97477

SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER

DATE OF INVESTIGATION: 5/7/2015

REPORT BY: JONATHAN B. DREW II, PLS 89396

ASSISTED BY: LANCE GOUCHER, SURVEY TECH.

ANDREW HILLMAN, SURVEY TECH.


THIS DOCUMENT FILED IN CS OFFICE:

YES

OTHER DOCUMENT FILED WITH CS:

NONE

CAP DIAGRAM:



C.S. File No 65/90-2