

FS INDEX ID: G-7

CORNER INVESTIGATION REPORT

CORNER: C 1/4 GCDB ID: 240540 DATE: 6/1/2015

TOWNSHIP: 31 S STATE: OREGON

RANGE: 1 W COUNTY: DOUGLAS

SECTION: 8 FOREST: UMPQUA

MERIDIAN: W.M. DISTRICT: TILLER


NFSL PROPERTY BOUNDARY CORNER?: YES NO

HISTORY OF VISITATIONS:
 1977-WILLIAM J. RUPPERT, M65-50
 2000-L.L. FANNING, USFS CORNER CARD

LINE(S) POSTED: SOUTH-1977 WEST-1977
MAINTAINED: SOUTH-2015 WEST-2015
GUARD POST(S): SOUTH-4.0 FT WEST-4.0 FT

CORNER HISTORY:

(1977)-ESTABLISHES CENTER 1/4 SECTION 8, SETS BRASS CAP/IRON PIPE & 2 BT'S.
 (2000)-FINDS BRASS CAP/IRON PIPE & 2 BT'S.



MONUMENT FOUND/SET:

FOUND A 2-1/2" BRASS CAP ON 2-1/2" GALVANIZED IRON PIPE, PROJECTING 3 INCHES ABOVE A MOUND OF STONE.

EXPIRES: 12/31/2015
RECORD MEASUREMENTS:

(N82°38'W - 36.2 FT)1977
 (S4°15'E - 13.9 FT)1977

RECORD CORNER ACCESSORIES:

A 18" FIR WITH A HEALED DOUBLE BLAZE.
 A 17" FIR WITH A HEALED DOUBLE BLAZE.

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES NEEDED.


METHOD OF MEASUREMENT:
 NO NEW MEASUREMENTS TAKEN

FILED AS CONDITION REPORT.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

CAP DIAGRAM:



GEODETTIC COORDINATES:

LATTITUDE: N 42° 53' 40.926"
 LONGITUDUE: W 122° 51' 12.576"
 ELIPSOID HEIGHT: 3115 FT
 DATUM: WGS84

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D
 SPRINGFIELD, OREGON 97477

SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER.

DATE OF INVESTIGATION: 4/28/2015

REPORT BY: JONATHAN B. DREW II, PLS 89396

ASSISTED BY: LANCE GOUCHER, SURVEY TECH.

THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No 65/90-4