

FS INDEX ID: J-3

CORNER INVESTIGATION REPORT

CORNER: 1/4
TOWNSHIP: 32S
RANGE: 1W
SECTION: 7 & 18
MERIDIAN: W.M.
GCDB ID: 140500
STATE: OREGON
COUNTY: DOUGLAS
FOREST: UMPQUA
DISTRICT: TILLER
NFSL PROPERTY BOUNDARY CORNER?: [x] YES [ ] NO

DATE: 6/1/2015

HISTORY OF VISITATIONS:

1883-R.S. MOORE, GLO SURVEY
1963-J.W. BYRON ET AL., CS 53/15
1979-K.O. DEGROOT, USFS CORNER CARD
1986-L.R. MOFFIT, USFS CORNER CARD
2004-R. WYTCHERLY, M144-50


LINE(S) POSTED: WEST-1979 EAST-1979
MAINTAINED: WEST-2015 EAST-2015
GUARD POST(S): WEST-2.5 FT EAST-4.0 FT

CORNER HISTORY:

(1883)-ESTABLISHED 1/4 CORNER, SETS POST & 2 BT'S.
(1963)-FINDS 1 BT, SETS BRASS CAP/IRON PIPE & 2 BT'S.
(1979)-FINDS BRASS CAP/IRON PIPE & 3 BT'S.
(1986)-FINDS BRASS CAP/IRON PIPE & 3 BT'S.
(2004)-FINDS BRASS CAP/IRON PIPE & 2 BT'S, SETS 2 NEW BT'S.

MONUMENT FOUND/SET:

FOUND A 2-1/2" DCSO BRASS CAP ON 1-1/4" GALVANIZED IRON PIPE, PROJECTING 7 INCHES ABOVE THE GROUND.



EXPIRES: 12/31/2015

RECORD CORNER ACCESSORIES:

NO TRACE FOUND OF A (9" FIR)1883
A ROOT HOLE & PINE REMAINS WITH NO MARKS REMAINING.
A 42" CEDAR WITH A HEALED DOUBLE BLAZE.
A 20" FIR WITH A HEALED DOUBLE BLAZE.
A 9" PINE WITH A PITCHED OVER PARTIALLY HEALED SINGLE BLAZE.
A 6" FIR WITH SCRIBE VISIBLE ON A PARTIALLY HEALED SINGLE BLAZE.

RECORD MEASUREMENTS:

(N13°E-9.9 FT)1883
(S10°W-9.9 FT)1883 & 1963
(S3°E-17.5 FT)1963, (S1°E)2004
(N74°W-51.2 FT)1963 & 2004
(S75°E-7.91 FT)2004
(N29°E-17.56 FT)2004

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES NEEDED.

METHOD OF MEASUREMENT:

NO NEW MEASUREMENTS TAKEN.

FILED AS CONDITION REPORT.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.


CAP DIAGRAM:

GEODETTIC COORDINATES:

LATTITUDE: N 42° 47' 43.825"
LONGITUDUE: W 122° 51' 48.251"
ELIPSOID HEIGHT: 2700 FT
DATUM: WGS 84

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D
SPRINGFIELD, OREGON 97477



SOURCE: USGS QUAD MAP. FOR NAVIGATION TO CORNER

DATE OF INVESTIGATION: 5/27/2015

REPORT BY: JONATHAN B. DREW II, PLS 89396

ASSISTED BY:

THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No 65/90-21