

CORNER INVESTIGATION REPORT

FS INDEX ID: J-3


CORNER: 1/4
TOWNSHIP: 31 S
RANGE: 1 W
SECTION: 7 & 18
MERIDIAN: W.M.
GCDB ID: 140500
STATE: OREGON
COUNTY: DOUGLAS
FOREST: UMPQUA
DISTRICT: TILLER
NFSL PROPERTY BOUNDARY CORNER?: [x] YES [] NO
LINE(S) POSTED: SOUTH-1972 NORTH-1977
MAINTAINED: SOUTH-2015 NORTH-2015
GUARD POST(S): SOUTH-4.9 FT NORTH-4.0 FT
CORNER HISTORY:

DATE: 4/24/2015

HISTORY OF VISITATIONS:

1857-DENNIS HATHORN, GLO SURVEY
1968-JOHN POWELL, ET. AL, CS 54/71
1972-J.A. HOFFBUHR, M42-80
1977-WILLIAM J. RUPPERT, M65-60
2003-L.E. HERZSTEIN, BLM RESURVEY

(1857)-ESTABLISHED 1/4 CORNER, SETS WOOD POST & 2 BT'S.
(1968)-FINDS NO TRACE OF 1/4 CORNER, SETS POST & TAG AT APPROX. LOCATION
(1972)-BY PROPORTION, SETS BRASS CAP/IRON POST & 2 BT'S.
(1977)-FINDS BRASS CAP/IRON PIPE 2 BT'S.
(2003)-FINDS & ACCEPTS BRASS CAP/IRON POST & 2 BT'S.
MONUMENT FOUND/SET:
FOUND A 3" BRASS CAP ON 2-1/2" GALVANIZED IRON PIPE, PROJECTING 1 INCH ABOVE A MOUND OF STONE.



RECORD CORNER ACCESSORIES:

NO TRACE FOUND OF A (18" LAUREL)1857
NO TRACE FOUND OF A (12" OAK)1857
A 15" FIR WITH A HEALED DOUBLE BLAZE.
A 17" FIR WITH A HEALED DOUBLE BLAZE.

EXPIRES: 12/31/2015
RECORD MEASUREMENTS:

(N85°E - 56.1')1857
(S83°E - 56.1')1857
(N49°45'W-39.3')1972,(N49°W-39.1')2003
(S33°W-37.6')1972, (S34°W-37.1')2003

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES NEEDED.

METHOD OF MEASUREMENT:


NO NEW MEASUREMENTS TAKEN.

FILED AS A CONDITION REPORT.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

CAP DIAGRAM:



GEODETIC COORDINATES:

LATITUDE: N42°53'14.148"
LONGITUDE: W122°52'24.222"
ELIPSOID HEIGHT:
DATUM: WGS 84

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D
SPRINGFIELD, OREGON 97477

SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER.

DATE OF INVESTIGATION: 4/21/2015

REPORT BY: JONATHAN B. DREW II, PLS 89396

ASSISTED BY: LANCE GOUCHER, SURVEY TECH.

THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No 65/90-22