

FS INDEX ID: D-25 & D-1

CORNER INVESTIGATION REPORT

CORNER: S 1/16 GCDB ID: 700620 & 100620 DATE: 5/25/2015
TOWNSHIP: 32S STATE: OREGON
RANGE: R2W & R1W COUNTY: DOUGLAS
SECTION: 1 & 6 FOREST: UMPQUA
MERIDIAN: W.M. DISTRICT: TILLER
NFSL PROPERTY BOUNDARY CORNER?: YES NO

HISTORY OF VISITATIONS:
 1970-B.A. SHANER, RM 2-21
 1980-L. HERZSTEIN, USFS CNR CARD

LINE(S) POSTED: SOUTH-1970 WEST-1970
MAINTAINED: SOUTH-2015 WEST-2015
GUARD POST(S): SOUTH-4.0 FT EAST-4.2 FT

CORNER HISTORY:
 (1970)-ESTABLISHED S1/16 CORNER, SETS BRASS CAP/IRON PIPE & 2 BT'S.
 (1980)-REPORTS CORNER OK & PLACE SIGNS ON 2 BT'S.

MONUMENT FOUND/SET:
 FOUND A 3" BRASS CAP ON A 2-1/2" GALVANIZED IRON PIPE. FLUSH IN A MOUND OF STONE.


RECORD CORNER ACCESSORIES:
 A 42" FIR WITH SCRIBE VISIBLE ON A PARTIALLY HEALED SINGLE BLAZE.
 A 22" CEDAR WITH A HEALED DOUBLE BLAZE.

NEW CORNER ACCESSORIES:
 NO NEW ACCESSORIES NEEDED.

CORNER MAINTENANCE/OTHER INFO:
 CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

GEODETIC COORDINATES:
LATTITUDE: N 42° 48' 52.117"
LONGITUDUE: W 122° 52' 24.027"
ELIPSOID HEIGHT: 2755 FT
DATUM: WGS 84
SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER.
DATE OF INVESTIGATION: 5/14/2015
REPORT BY: JONATHAN B. DREW II, PLS 89396
ASSISTED BY: LANCE GOUCHER, SURVEY TECH.
 ANDREW HILLMAN, SURVEY TECH.

DOCUMENTS ON FILE AT:
 3106 PIERCE PARKWAY, STE. D
 SPRINGFIELD, OREGON 97477




EXPIRES: 12/31/2015
RECORD MEASUREMENTS:
 (N89°30'W-41.6 FT)1970
 (S88°E-8.2 FT)1970

METHOD OF MEASUREMENT:
 NO NEW MEASUREMENTS TAKEN.

FILED AS CONDITION REPORT.

CAP DIAGRAM:



THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No 65/90-26