

FS INDEX ID: E-24

CORNER INVESTIGATION REPORT

CORNER: E 1/16 GCDB ID: 660600
TOWNSHIP: 32S STATE: OREGON
RANGE: 2W COUNTY: DOUGLAS
SECTION: 1 & 12 FOREST: UMPQUA
MERIDIAN: W.M. DISTRICT: TILLER
NFSL PROPERTY BOUNDARY CORNER?: YES NO

DATE: 6/1/2015

HISTORY OF VISITATIONS:
 1970-B.A. SHANER, RM 2-21
 1980-L. HERZSTEIN, USFS CNR CARD

LINE(S) POSTED: NORTH-1970 WEST-1970
MAINTAINED: NORTH-2015 WEST-2015
GUARD POST(S): NORTH WEST

CORNER HISTORY:
 (1970)-ESTABLISHED E1/16 CORNER, SETS BRASS CAP/IRON PIPE & 2 BT'S
 (1980)-REPORTS CORNER OK, PLACED SIGNS ON 2 BT'S.

MONUMENT FOUND/SET:
 FOUND A 3" BRASS CAP ON 2-1/2" GALVANIZED IRON PIPE, PROJECTING 4" ABOVE A MOUND OF STONE.


RECORD CORNER ACCESSORIES:
 A 19" FIR WITH A HEALED SINGLE BLAZE.
 A 35" FIR WITH A HEALED SINGLE BLAZE.

NEW CORNER ACCESSORIES:
 NO NEW ACCESSORIES NEEDED.

CORNER MAINTENANCE/OTHER INFO:
 CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

GEODETIC COORDINATES:
LATTITUDE: N 42° 48' 39.189"
LONGITUDUE: W 122° 52' 41.194"
ELIPSOID HEIGHT: 2980 FT
DATUM: WGS 84
SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER.
DATE OF INVESTIGATION: 5/14/2015
REPORT BY: JONATHAN B. DREW II, PLS 89396
ASSISTED BY: LANCE GOUCHER, SURVEY TECH.
 ANDREW HILLMAN, SURVEY TECH.


DOCUMENTS ON FILE AT:
 3106 PIERCE PARKWAY, STE. D
 SPRINGFIELD, OREGON 97477



RECORD MEASUREMENTS:
 EXPIRES: 12/31/2015
 (N46°E-17.0')1970
 (S4°30'E-84.2')1970

METHOD OF MEASUREMENT:
 NO NEW MEASUREMENTS TAKEN.
 GUARD POSTS PRESENT BUT NOT MEASURED.

FILED AS CONDITION REPORT.



THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No. 65/90-32