

FS INDEX ID: A.5-19

CORNER INVESTIGATION REPORT

CORNER: CNN 1/64
TOWNSHIP: 31S
RANGE: 2W
SECTION: 2
MERIDIAN: W.M.

GCDB ID: 540670
STATE: OREGON
COUNTY: DOUGLAS
FOREST: UMPQUA
DISTRICT: TILLER

DATE: 7/7/2015

HISTORY OF VISITATIONS:

1978-G.S. BAUGHMAN, M65-68
2009-USFS SURVEY CREW, NO RECORD

NFSL PROPERTY BOUNDARY CORNER?: YES NO

LINE(S) POSTED: SOUTH-1978 WEST-1978

MAINTAINED: SOUTH-2009 WEST-2009

GUARD POST(S): SOUTH-NONE WEST-NONE

CORNER HISTORY:

(1978)-ESTABLISHED CNN 1/64 CORNER, SETS BRASS CAP/IRON PIPE & 2 BT'S.

MONUMENT FOUND/SET:

FOUND A 3" BRASS CAP ON 2-1/2" GALVANIZED IRON PIPE, PROJECTING 4 INCHES ABOVE THE GROUND.

NOTE: CAP SHOWS "T31S R2 WM", SHOULD READ "T31S R2W WM"

RECORD CORNER ACCESSORIES:

A 23" FIR SNAG BEARS, S17°E - 153.6 FT, WITH A HEALED DOUBLE BLAZE.
A 14" PINE STUMP BEARS, N4°45'W - 58.9 FT, WITH NO MARKS VISIBLE.

NEW CORNER ACCESSORIES:

A 7" OAK BEARS, N3°15'E - 122.6 FT, MARKED "CNN1/64S2BT" ON A SINGLE BLAZE.
A 23" OAK BEARS, S40°45'E - 102.5 FT, MARKED CNN1/64S2BT" ON A SINGLE BLAZE.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

NEW BT'S INCLUDE A 3/4" BRASS WASHER, "ORPLS#89396" NAILED BETWEEN B & T.

GEODETIC COORDINATES:

LATITUDE: N 42° 54' 53.023"

LONGITUDE: W 122°54' 45.954"

ELLIPSOID HEIGHT: 2350 FT

DATUM: WGS 84

SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER.

DATE OF INVESTIGATION: 6/24/2015

REPORT BY: JONATHAN B. DREW II, PLS#89396, CFedS#1664

ASSISTED BY: ANDREW HILLMAN, SURVEY TECH.

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D

SPRINGFIELD, OREGON 97477

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
DECEMBER 3, 2014
JONATHAN B. DREW II
89396

EXPIRES: 12/31/2015


RECORD MEASUREMENTS:

(S14°E-153.0 FT)1978
(N5°30'W-59.2 FT)1978

METHOD OF MEASUREMENT:

LEICA TCR 1201+ TOTAL STATION
HOLD N89°31'58"W ON A STEEL POST
FOUND WEST OF CORNER. BEARINGS
TO CENTER. DISTANCES TO NAIL SET
SIDE CENTER.

CAP DIAGRAM:



THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No 65/90-34