

FS INDEX ID: T-7

CORNER INVESTIGATION REPORT

CORNER: C 1/4
TOWNSHIP: 31 S
RANGE: 1 W
SECTION: 29
MERIDIAN: W.M.
NFSL PROPERTY BOUNDARY CORNER?: YES NO

GCDB ID: 240240
STATE: OREGON
COUNTY: DOUGLAS
FOREST: UMPQUA
DISTRICT: TILLER

DATE: 7/27/2015

HISTORY OF VISITATIONS:

1972-J.A. HOFFBUHR, M42-70
 1981-J. LANDRUM, USFS CORNER CARD

LINE(S) POSTED: NORTH-1972 SOUTH-1972
MAINTAINED: NORTH-2015 SOUTH-2015
GUARD POST(S): NORTH-30.1 FT SOUTH-5.0 FT

CORNER HISTORY:


(1972)-ESTABLISHES C 1/4 SECTION 29, SETS BRASS CAP/IRON PIPE & 2 BT'S.
 (1981)-ATTACHED SIGNS TO GUARD POSTS AND BT'S, NOTES CORNER IN GOOD CONDITION.

MONUMENT FOUND/SET:

FOUND A 3" BRASS CAP ON 2-1/2" GALVANIZED IRON PIPE, PROJECTING 4 INCHES ABOVE A MOUND OF STONE.

RECORD CORNER ACCESSORIES:

A 16" FIR BEARS, S71°15'W - 7.2 FT, WITH A HEALED DOUBLE BLAZE, TREE LEANS HEAVY TO THE WEST.
 A 19" FIR BEARS, N56°30'E - 20.5 FT, WITH A HEALED DOUBLE BLAZE.



EXPIRES: 12/31/2015

RECORD MEASUREMENTS:

(S75°15'W - 6.9 FT)1972
 (N57°E - 20.5 FT)1972

FILED

Date: 8-25-2015 By: JC
 This survey consists of:
 Map: _____
 Narrative: _____
 Corner Bk: CS 65/90-58

NEW CORNER ACCESSORIES:


NO NEW ACCESSORIES ADDED.

DOUGLAS COUNTY
 SURVEYOR

METHOD OF MEASUREMENT:

LEICA 1103+ TOTAL STATION, BASIS OF BEARING: MEAN GEODETIC. BEARINGS TO CENTER, DISTANCES TO NAIL SET SIDE CENTER. A TRUE LINE TRAVERSE WAS RUN THRU THIS CORNER NORTH TO CN1/16 S29 AND SOUTH TO WC 1/4 Sec 29/32.

CAP DIAGRAM:



CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

TIE: CN 1/16 S29 BEARS N0°9'47"E - 1350.73 FT, (N0°9'59"E-1350.86 FT)1972

TIE: WC 1/4 S29/32 BEARS S0°9'28"W - 2648.84 FT, (S0°9'59"W-2648.60 FT)1972

GEODETIC COORDINATES:
DOCUMENTS ON FILE AT:
 LATITUDE: N 42° 51' 02.35462" 3106 PIERCE PARKWAY, STE. D
 LONGITUDE: W 122° 51' 12.67035" SPRINGFIELD, OREGON 97477
 ELLIPSOID HEIGHT: 1812.3 FT

DATUM: NAD_83(2011)(EPOCH:2010.0000)

SOURCE: TRAVERSE TIE FROM GPS @ WC1/4 & CN1/16 S29. OPUS CORRECTED BASE

DATE OF INVESTIGATION: 7/14/2015

REPORT BY: JONATHAN B. DREW II, PLS#89396, CFedS#1664

ASSISTED BY: ANDREW HILLMAN, SURVEY TECH

THIS DOCUMENT FILED IN CS OFFICE: YES
OTHER DOCUMENT FILED WITH CS: MAP/PLAT

C.S. FILE NO 65/90-58