

FS INDEX ID: X-17

# CORNER INVESTIGATION REPORT

CORNER: 1/4                      GCDB ID: 500140  
TOWNSHIP: 31S                 STATE: OREGON  
RANGE: 1W                      COUNTY: DOUGLAS  
SECTION: 34 & 35             FOREST: UMPQUA  
MERIDIAN: W.M.               DISTRICT: TILLER  
NFSL PROPERTY BOUNDARY CORNER?:  YES  NO

DATE: 6/9/2015

HISTORY OF VISITATIONS:  
1857-DENNIS HATHORN, GLO SURVEY  
1922-FRED MENSCH, GLO RESURVEY  
1968-JOHN M. POWELL ET AL., CS 54/71  
1980-K.C. WEAVER, M83-4A-D  
1985-L. MOFFIT, USFS CORNER CARD

LINE(S) POSTED: NORTH-1985 WEST-1980  
MAINTAINED: NORTH-2015 WEST-2015  
GUARD POST(S): NORTH-3.5 FT WEST-2.2 FT

CORNER HISTORY:

- (1857)-ESTABLISHED 1/4, SET POST & 2 BT'S.
- (1922)-FINDS 2 BT'S., SETS BRASS CAP/IRON PIPE & 2 BT'S.
- (1968)-FINDS BRASS CAP/IRON PIPE & 2 BT'S, MARKS 2 NEW BT'S.
- (1980)-FINDS BRASS CAP/IRON PIPE & 4 BT'S.
- (1985)-FINDS BRASS CAP/IRON PIPE AND 3 BT'S.

MONUMENT FOUND/SET:

FOUND A 2-1/2" BRASS CAP ON 1" IRON PIPE PROJECTING 8 INCHES ABOVE THE GROUND.

RECORD CORNER ACCESSORIES:

- NO TRACE FOUND OF A (12" OAK)1857
- A 37" OAK SNAG WITH NO MARKS VISIBLE AND NO BARK REMAINING.
- NO TRACE FOUND OF A (14" B.OAK)1922
- ROTTEN REMAINS OF AN INDETERMINATE SIZE OAK.
- A 18" FIR WITH A HEALED DOUBLE BLAZE.
- A 18" FIR WITH A HEALED DOUBLE BLAZE.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**



OREGON  
DECEMBER 3, 2014  
**JONATHAN B. DREW II**  
89396

EXPIRES: 12/31/2015

RECORD MEASUREMENTS:

- (S18°W - 46.2 FT)1857
- (S68°E - 83.8 FT)1857
- (S66°E-27.7')1922, (S70°35'E-27.1')1980
- (S24°W-48.2')1922, (S19°25'W-47.3')1980
- (N43°E-14.2')1968, (N44°17'E-14.3')1980
- (S10°W-7.4')1968, (S9°59'W-7.7')1980

**FILED**

Date: 8-25-2015 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65 / 90-63

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES ADDED.

METHOD OF MEASUREMENT:

NO NEW MEASUREMENTS TAKEN.

**DOUGLAS COUNTY  
SURVEYOR**

FILED AS CONDITION REPORT.

CORNER MAINTENANCE/OTHER INFO:

- CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT, ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

GEODETIC COORDINATES:

LATITUDE: N 42° 50' 09.593"  
LONGITUDE: W 122° 48' 13.615"  
ELLIPSOID HEIGHT: 3180 FT  
DATUM: WGS 84

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D  
SPRINGFIELD, OREGON 97477

SOURCE: CELL PHONE GPS, FOR NAVIGATION TO CORNER.

DATE OF INVESTIGATION: 6/8/2015


REPORT BY: JONATHAN B. DREW II, PLS#89396, CFedS#1664

ASSISTED BY: ANDREW HILLMAN, SURVEY TECH.

THIS DOCUMENT FILED IN CS OFFICE: YES

OTHER DOCUMENT FILED WITH CS: NONE

CAP DIAGRAM:



**C.S. File No** 65/90-63