

FS INDEX ID: X-21

CORNER INVESTIGATION REPORT

CORNER: 1/4
TOWNSHIP: 30S
RANGE: 2W
SECTION: 35 & 36
MERIDIAN: W.M.
NFSL PROPERTY BOUNDARY CORNER?: YES NO
LINE(S) POSTED: SOUTH-1978 NORTH-1978
MAINTAINED: SOUTH-2015 NORTH-1985
GUARD POST(S): SOUTH NORTH

GCDB ID: 600140
STATE: OREGON
COUNTY: DOUGLAS
FOREST: UMPQUA
DISTRICT: TILLER

DATE: 7/7/2015

HISTORY OF VISITATIONS:

1857-DENNIS HATHORN, GLO SURVEY
 1968-JOHN M. POWELL ET AL., CS 54/73
 1978-G.S. BAUGHMAN, M65-56
 1985-L. MOFFIT, USFS CORNER CARD
 2000-L. FANNING, USFS CORNER CARD


CORNER HISTORY:

(1857)-ESTABLISHED 1/4 CORNER, SETS POST WITH STONE MOUND & 2 BT'S.
 (1968)-FINDS 2 BT'S, SETS BRASS CAP/IRON PIPE & 2 BT'S.
 (1978)-FINDS BRASS CAP/IRON PIPE & 4 BT'S.
 (1985)-FINDS BRASS CAP/IRON PIPE & 2 BT'S.
 (2001)-FINDS BRASS CAP/IRON PIPE & 4 BT'S.

MONUMENT FOUND/SET:

FOUND A 2-1/2" BRASS CAP ON 1-1/4" GALVANIZED IRON PIPE, PROJECTING 8" ABOVE THE GROUND.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR



OREGON
 DECEMBER 3, 2014
 JONATHAN B. DREW II
 89396

EXPIRES: 12/31/2015

RECORD MEASUREMENTS:

(N14°W-11.9 FT)1857
 (N26°E-11.2 FT)1857
 (S51°E-13.0 FT)1968
 (N62°W-15.2 FT)1968

RECORD CORNER ACCESSORIES:

A (24" FIR)1857. (DOWN FIR)1968, NOT SEARCHED FOR.
 A 36" FIR STUMP WITH A HEALED SINGLE BLAZE.
 A 18" FIR WITH A HEALED DOUBLE BLAZE.
 A 18" FIR WITH A HEALED DOUBLE BLAZE.

FILED

Date: 8-25-2015 By: X

This survey consists of:

Map: _____

Narrative: _____

Corner Rpt. CS 65/90-66

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES ADDED.

DOUGLAS COUNTY
 SURVEYOR

METHOD OF MEASUREMENT:


NO NEW MEASUREMENTS TAKEN.
 GUARD POSTS PRESENT, NOT
 MEASURED.

FILED AS CONDITION REPORT.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO
 MONUMENT AND GUARD POSTS, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT,
 ADD NEW NAILS TO EXISTING BT TAGS & ADD NEW TAGS WHERE NEEDED.

CAP DIAGRAM:



GEODETTIC COORDINATES:

LATITUDE: N 42° 55' 25.868"
 LONGITUDE: W 122° 54' 10.607"
 ELLIPSOID HEIGHT: 2625 FT
 DATUM: WGS 84

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D
 SPRINGFIELD, OREGON 97477

SOURCE: USGS QUAD MAP, FOR NAVIGATION TO CORNER.

DATE OF INVESTIGATION: 6/8/2015

REPORT BY: LANCE GOUCHER, SURVEY TECH.

ASSISTED BY: ANDREW HILLMAN, SURVEY TECH.

THIS DOCUMENT FILED IN CS OFFICE: YES

OTHER DOCUMENT FILED WITH CS: NONE

C.S. File No 65/90-66