

FILED
DATE: 11-8-2016 BY: JC
THIS SURVEY CONSISTS OF:
MAP: _____
NARRATIVE: _____
CORNER RPT: CS 65/93-40
DOUGLAS COUNTY SURVEYOR

FS INDEX ID: C-19

CORNER INVESTIGATION REPORT

CORNER: C 1/4
TOWNSHIP: 31 S
RANGE: 2 W
SECTION: 2
MERIDIAN: W.M.
GCDB ID: 540640
STATE: OREGON
COUNTY: DOUGLAS
FOREST: UMPQUA
DISTRICT: TILLER
NFSL PROPERTY BOUNDARY CORNER?: YES NO

DATE: 9/13/2016

HISTORY OF VISITATIONS:
1978 - G.S. BAUGHMAN, M65-68

LINE(S) POSTED: NORTH-1978 SOUTH-1978
MAINTAINED: NORTH-2016 SOUTH-2016
GUARD POST(S): SOUTH-6.6 FT

CORNER HISTORY:

(1978) - ESTABLISHED CORNER, SET IRON PIPE/BRASS CAP & 2 BT'S.

MONUMENT FOUND/SET:

FOUND A 2" IRON PIPE WITH A 2-1/2" BRASS CAP, FLUSH IN A MOUND OF STONE.

RECORD CORNER ACCESSORIES:

A 11" FIR WITH A HEALED DOUBLE BLAZE.
A 16" FIR WITH A HEALED DOUBLE BLAZE.

NEW CORNER ACCESSORIES:

NO NEW ACCESSORIES ADDED.

CORNER MAINTENANCE/OTHER INFO:

CLEAR BRUSH FROM AROUND MONUMENT AND TO BT'S. TIE FLAGGING TO MONUMENT AND GUARD POST, PAINT BT FACES & A 6" BAND AT HEAD HEIGHT,

GEODETIC COORDINATES:

LATITUDE: N 42° 54' 32.968"
LONGITUDE: W 122° 54' 46.335"
ELLIPSOID HEIGHT:

DATUM: NAD 83

SOURCE: POST PROCESSED RESOURCE GRADE, AS REPORTED BY JACK SNYDER.


DATE OF INVESTIGATION: 8/30/2016

REPORT BY: ANDREW HILLMAN, SURVEY TECH.

ASSISTED BY: JACOB HUNT, SURVEY TECH.

DOCUMENTS ON FILE AT:

3106 PIERCE PARKWAY, STE. D
SPRINGFIELD, OREGON 97477



EXPIRES: 12/31/2017

RECORD MEASUREMENTS:


(N36°W - 65.7 FT)1978
(S26°W - 44.6 FT)1978

METHOD OF MEASUREMENT:

NO NEW MEASUREMENTS TAKEN.

FILED AS CONDITION REPORT.

CAP DIAGRAM:



THIS DOCUMENT FILED IN CS OFFICE:

YES

OTHER DOCUMENT FILED WITH CS:

NONE

C.S. File No 65/93-40