


PUBLIC LAND CORNER

INDEX NO. _____

WEYERHAEUSER COMPANY
WILLAMETTE REGION



TOWNSHIP 23S RANGE 4W
SECTION 24 CORNER CENTER 1/4
COUNTY DOUGLAS OREGON

ORIGINAL CORNER DATED: 1987 BY: DONALD BRANCH M104-1
CORNER: 5/8" X 30" IRON ROD WITH L/S CAP

ACCESSORIES: _____
SPIKE IN STUMP, S80°30'36"E, 29.37 FEET
SPIKE IN STUMP, N0°56'W, 22.60 FEET

REESTABLISHMENT NOTES DATED: _____ BY: _____
EVIDENCE RECOVERED: _____ **FILED**

CORNER SET: _____ Date: 1-12-2017 By: VC
This survey consists of: _____

ACCESSORIES ESTABLISHED: _____
Map: _____
Narrative: _____
Corner Rpt.: CS 65/95-6

REESTABLISHMENT NOTES DATED: _____ BY: _____
EVIDENCE RECOVERED: _____ **DOUGLAS COUNTY SURVEYOR**

CORNER SET: _____
ACCESSORIES ESTABLISHED: _____

REESTABLISHMENT NOTES DATED: 4/7/2015 BY: KEN HOFFINE CS FILE 65/89-16
EVIDENCE RECOVERED: 5/8" IRON ROD WITH YELLOW PLASTIC CAP SET BY BRANCH
REFERENCE SPIKE IN ROTTEN STUMP, S80°27'35"E, 29.38 FEET

CORNER SET: NOTHING
ACCESSORIES ESTABLISHED: _____

8" FIR, S86 1/2°E, 25.1 FEET - SCRIBED "C1/4S24 BT"
6" FIR, S3 1/2°W, 24.6 FEET - SCRIBED "C1/4S24 BT"
6" FIR, N18 3/4°W, 6.45 FEET - SCRIBED "C1/4S24 BT"

REMONUMENTATION

DATE: 6/2015 BY: DANIEL W. BAKER TITLE: PLS 1978 FIRM: BAKER & ASSOC.
EVIDENCE RECOVERED: 5/8" IRON ROD AND YELLOW PLASTIC CAP "BRANCH"

10" FIR, S 86° E, 25.1 FEET TO CENTER
8" FIR, S 3° W, 24.5 FEET TO CENTER
8" FIR, N 18° W, 6.5 FEET TO CENTER / SPIKE IN 24" FIR STUMP, S 80° E, 29.4 FEET

CORNER SET: NONE
ACCESSORIES ESTABLISHED: _____

OTHER INFORMATION: SET 6 FOOT STEEL POST ALONGSIDE CORNER