

FILED  
Date: 3/30/2017 By: JC

This survey consists of:

Map: \_\_\_\_\_

Narrative: \_\_\_\_\_

Corner Rpt: CS 65/95-27

DOUGLAS COUNTY  
SURVEYOR

CORNER REPORT FORM

Section 12 Township 30 S Range 2 W  
Douglas County Date 2/20/17  
PLSS Number 640500

CORNER DESIGNATION

South 1/4 corner of Section 12 only.

\_\_\_ Condition Report only  
\_\_\_ Not Found  
X Renewed  
\_\_\_ Unrecorded  
\_\_\_ Surveyed In  
\_\_\_ Referenced out

Previous Renewals/Surveys, etc.

Original set by Mensch in 1908. Renewed by Markham 3/24/60 on C.S. 42/421.  
D.C.S. renewal in 1978. Used by B.L.M. in 1998 and Shaner in 2001 on M 132-75.

Monument(s) & Accessories Found: (Condition and Source)

Standard 1978 D.C.S. brass capped iron pipe in good condition.

Bearing trees by Markham: A 20" diam. Cedar with healed blaze bears

S. 20 3/4° W., 36.3'

A 25" diam. high Cedar stump with healed blaze bears

N. 46° W, 40.9'

No other previous accessories remain.

Monument Detail

Sketch

Standard 1978 D.C.S. brass capped iron pipe.

Monument Set (Procedures and Description)

N/A

New Accessories

An 8" diam. Fir scribed "1/4 S12 BT" bears N. 66° W., 16.5 feet.

A six foot steel post is set 2 feet North.

Surveyor's Seal

Location & Comments

Compass Declination 15° East

Firm/Agency: David Edwards Land Surveying


Address: P.O. Box 361

Oakland, Oregon 97462

Party Chief: Brant Miller

Notes: \_\_\_\_\_

Witness: Eric Sprinkle



Renews 12/31/17

C.S. File 65/95-27